



August 29, 2003

State of Utah
Division of Oil, Gas & Mining
Attn: Diana Mason
1594 West North Temple - Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Applications for Permit to Drill: Federal 1-12-9-17, 3-12-9-17, 5-12-9-17, 7-12-9-17, 9-12-9-17, 11-12-9-17, 13-12-9-17, and 15-12-9-17.

Dear Diana:

Enclosed find APD's on the above referenced wells. If you have any questions, feel free to give either Brad or myself a call.

Sincerely,

Mandie Crozier
Regulatory Specialist

mc
enclosures

RECEIVED
SEP 02 2003
DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004

5. Lease Serial No.

U-39713

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA Agreement, Name and No.

N/A

8. Lease Name and Well No.

Federal 15-12-9-17

9. API Well No.

43-047-35169

10. Field and Pool, or Exploratory

Monument Butte Eight miles flat

11. Sec., T., R., M., or Blk. and Survey or Area

SW/SE Sec. 12, T9S R17E

12. County or Parish

Uintah

13. State

UT

1a. Type of Work: ☒ DRILL

☐ REENTER

1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other

☒ Single Zone ☐ Multiple Zone

2. Name of Operator

Inland Production Company

3a. Address

Route #3 Box 3630, Myton UT 84052

3b. Phone No. (include area code)

(435) 646-3721

4. Location of Well (Report location clearly and in accordance with any State requirements.)*

At surface SW/SE 659' FSL 1981' FEL 4432517Y 40.04004
At proposed prod. zone 589412X -109.95195

14. Distance in miles and direction from nearest town or post office*

Approximatley 17.0 miles southeast of Myton, Utah

15. Distance from proposed*

location to nearest
property or lease line, ft.

(Also to nearest drig. unit line, if any) Approx. 1981' f/lse, NA f/unit

16. No. of Acres in lease

1,120.00

17. Spacing Unit dedicated to this well

40 Acres

18. Distance from proposed location*
to nearest well, drilling, completed,
applied for, on this lease, ft.

Approx. 2503'

19. Proposed Depth

6500'

20. BLM/BIA Bond No. on file

#4488944

21. Elevations (Show whether DF, KDB, RT, GL, etc.)

5097' GR

22. Approximate date work will start*

4th Quarter 2003

23. Estimated duration

Approximately seven (7) days from spud to rig release.

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature

Mandie Crozier

Name (Printed/Typed)

Mandie Crozier

Date

8/29/03

Title

Regulatory Specialist

Approved by (Signature)

Name (Printed/Typed)

BRADLEY G. HILL

Date

09-04-03

Title

Off ENVIRONMENTAL SCIENTIST III

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

RECEIVED

SEP 02 2003

DIV. OF OIL, GAS & MINING

INLAND PRODUCTION COMPANY

Λ

THIS IS TO CERTIFY THAT THE LARGE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
No. 189377

STACY W.
SILWART

REGISTERED LAND SURVEYOR
REGISTRATION NO. 189377
STATE OF UTAH

38 WEST 100 NORTH - VERNAL, UTAH 84078
(435) 781-2501

SURVEYED BY: C.D.S./K.G.S.

DRAWN BY: J.R.S.

FILE #



= SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (PARIETTE DRAW SW)

INLAND PRODUCTION COMPANY
FEDERAL #15-12-9-17
SW/SE SECTION 12, T9S, R17E
UINTAH COUNTY, UTAH

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta	0' – 1640'
Green River	1640'
Wasatch	5875'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation 1640' – 6500' - Oil

4. PROPOSED CASING PROGRAM

Please refer to the Monument Butte Field Standard Operation Procedure (SOP).

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

Please refer to the Monument Butte Field SOP. See Exhibit "C".

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

Please refer to the Monument Butte Field SOP.

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Please refer to the Monument Butte Field SOP.

8. TESTING, LOGGING AND CORING PROGRAMS:

Please refer to the Monument Butte Field SOP.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

The anticipated maximum bottom hole pressure is 2000 psi. It is not anticipated that abnormal temperatures will be encountered.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

Please refer to the Monument Butte Field SOP.

**INLAND PRODUCTION COMPANY
FEDERAL #15-12-9-17
SW/~~SE~~ SECTION 12, T9S, R17E
UINTAH COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Inland Production Company well location site Federal #15-12-9-17 located in the SW 1/4 SE 1/4 Section 12, T9S, R17E, Uintah County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.6 miles \pm to the junction of this highway and UT State Hwy 53; proceed southeasterly along Hwy 53 - 11.8 miles \pm to it's junction with an existing road to the southeast; proceed southeasterly - 3.6 miles \pm to it's junction with the beginning of an access road to be upgraded; proceed northeasterly along the proposed access road to be upgraded 450' \pm to the proposed well location.

2. PLANNED ACCESS ROAD

See Topographic Map "B" for the location of the proposed access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

Please refer to the Monument Butte Field Standard Operating Procedure (SOP).

5. LOCATION AND TYPE OF WATER SUPPLY

Please refer to the Monument Butte Field SOP. See Exhibit "A".

6. SOURCE OF CONSTRUCTION MATERIALS

Please refer to the Monument Butte Field SOP.

7. METHODS FOR HANDLING WASTE DISPOSAL

Please refer to the Monument Butte Field SOP.

8. ANCILLARY FACILITIES

Please refer to the Monument Butte Field SOP.

9. **WELL SITE LAYOUT**

See attached Location Layout Diagram.

10. **PLANS FOR RESTORATION OF SURFACE**

Please refer to the Monument Butte Field SOP.

11. **SURFACE OWNERSHIP** - Bureau Of Land Management

12. **OTHER ADDITIONAL INFORMATION**

The Paleontological Resource Survey and Archaeological Resource Survey for this area are attached. MOAC Report #03-58, 5/19/03. Paleontological Resource Survey prepared by, Wade E. Miller, 5/8/03. See attached report cover pages, Exhibit "D".

Inland Production Company requests a 60' ROW for the Federal #15-12-9-17 to allow for construction of a 6" gas gathering line, and a 3" poly fuel gas line. Both lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

Inland Production Company also requests a 60' ROW be granted for the Federal #15-12-9-17 to allow for construction of a 3" steel water injection line and a 3" poly water return line. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

Water Disposal

Please refer to the Monument Butte Field SOP.

Reserve Pit Liner

Please refer to the Monument Butte Field SOP.

Location and Reserve Pit Reclamation

Please refer to the Monument Butte Field SOP.

The following seed mixture will be used on the topsoil stockpile, the recontoured surface of the reserve pit, and for final reclamation: (All poundages are in pure live seed)

Shadscale	<i>Atriplex confertifolia</i>	6 lbs/acre
Galleta grass	<i>Hilaria jamesii</i>	6 lbs/acre

13. **LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION**

Representative

Name: Brad Mecham

Address: Route #3 Box 3630
Myton, UT 84052

Telephone: (435) 646-3721

Certification

Please be advised that INLAND PRODUCTION COMPANY is considered to be the operator of well #15-12-9-17 SW/SE Section 12, Township 9S, Range 17E: Lease U-39713 Uintah County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4488944.

I hereby certify that the proposed drillsite and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Inland Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

8/29/03


Date

Mandie Crozier
Mandie Crozier
Regulatory Specialist

INLAND PRODUCTION COMPANY

FEDERAL 15-12-9-17

Section 12, T9S, R17E, S.L.B.&M.



SURVEYED BY: K.G.S.

SCALE: 1" = 50'

DRAWN BY: J.R.S.

DATE: 5-20-03

Tri State
Land Surveying, Inc.





38 WEST 100 NORTH VERNAL, UTAH 84078

(435) 781-2501

INLAND PRODUCTION COMPANY

CROSS SECTIONS

FEDERAL 15-12-9-17



NOTE:
UNLESS OTHERWISE NOTED
ALL CUT/FILL SLOPES ARE
AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES

(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	660	660	Topsoil is not included in Pad Cut	0
PIT	640	0		640
TOTALS	1,300	660	890	640

SURVEYED BY: K.G.S.

SCALE: 1" = 50'

DRAWN BY: J.R.S.

DATE: 5-20-03


Tri State
Land Surveying, Inc.
38 WEST 100 NORTH VERNAL, UTAH 84078

(435) 781-2501

INLAND PRODUCTION COMPANY

TYPICAL RIG LAYOUT

FEDERAL 15-12-9-17



SURVEYED BY: K.G.S.

SCALE: 1" = 50'


DRAWN BY: J.R.S.

DATE: 5-20-03

Tri State
Land Surveying, Inc.

(435) 781-2501

38 WEST 100 NORTH VERNAL, UTAH 84078



**Federal 15-12-9-17
SEC. 12, T9S, R17E, S.L.B.&M.**




**Tri-State
Land Surveying Inc.**
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1 = 100,000
DRAWN BY: R.A.B.
DATE: 05-23-2003

Legend
Existing Road
Proposed Access

TOPOGRAPHIC MAP

"A"



**Federal 15-12-9-17
SEC. 12, T9S, R17E, S.L.B.&M.**




**Tri-State
Land Surveying Inc.**
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: R.A.B.
DATE: 05-23-2003

Legend
Existing Road
Upgraded Access

TOPOGRAPHIC MAP

"B"



Federal 15-12-9-17
SEC. 12, T9S, R17E, S.L.B.&M.



Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078


SCALE: 1" = 2,000'
 DRAWN BY: R.A.B.
 DATE: 05-23-2003

Legend


- Roads
- - - Proposed Gas Line
- - - Proposed Water Line

TOPOGRAPHIC MAP

"C"



January 15, 2003



**Federal 15-12-9-17
SEC. 12, T9S, R17E, S.L.B.&M.**



**Tri-State
Land Surveying Inc.**
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: R.A.B.

DATE: 05-23-2003

Legend

- Well Locations
- One-Mile Radius

Exhibit "B"

2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

CULTURAL RESOURCE INVENTORY OF
INLAND RESOURCES' BLOCK PARCELS IN
T 9S, R 17E, SECTIONS 1 AND 12
Uintah County, Utah

BY:

Mark C. Bond

Prepared For:

Bureau of Land Management
Vernal Field Office

Prepared Under Contract With:

Jon D. Holst & Company
for
Inland Resources
2507 Flintridge Place
Fort Collins, CO 80521

Prepared By:

Montgomery Archaeological Consultants
P.O. Box 147
Moab, Utah 84532

MOAC Report No. 03-58

May 19, 2003

United States Department of Interior (FLPMA)
Permit No. 03-UT-60122

State of Utah Antiquities Project (Survey)
Permit No. U-03-MQ-0328b

INLAND RESOURCES, INC.

**PALEONTOLOGICAL FIELD SURVEY OF PROPOSED
PRODUCTION DEVELOPMENT AREAS,
DUCHESNE AND UTAH COUNTIES, UTAH**

(South ½ Section 6, T 9 S, R 18 E; South ½ Section 1, T 9 S, R 17 E;
all of Sections 11 and 12, the NW, SE & NE quarters of the SW ¼ Section 10,
the NE ¼ & SE ¼ of the SE ¼ Section 9, T 9 S, R 17 E and the SE ¼, SW ¼,
NE ¼ and SE ¼ of the SE ¼, Section 33, T 8 S, R 17 E.)

REPORT OF SURVEY

Prepared for:

Inland Resources, Inc.

Prepared by:

Wade E. Miller
Consulting Paleontologist
May 8, 2003

003

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 09/02/2003

API NO. ASSIGNED: 43-047-35169

WELL NAME: FEDERAL 15-12-9-17

OPERATOR: INLAND PRODUCTION (N5160)

CONTACT: MANDIE CROZIER

PHONE NUMBER: 435-646-3721

PROPOSED LOCATION:

SWSE 12 090S 170E

SURFACE: 0659 FSL 1981 FEL

BOTTOM: 0659 FSL 1981 FEL

UINTAH

8 MILE FLAT NORTH (590)

LEASE TYPE: 1 - Federal

LEASE NUMBER: U-39713

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: GRRV

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LATITUDE: 40.04004

LONGITUDE: 109.95195


RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. 4488944)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. MUNICIPAL)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

___ R649-2-3.
Unit _____
☒ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
___ R649-3-3. Exception
___ Drilling Unit
Board Cause No: _____
Eff Date: _____
Siting: _____
___ R649-3-11. Directional Drill

COMMENTS: SOP, Seperate fileSTIPULATIONS: 1- Federal approval
2- Spacing Strip




OPERATOR: INLAND PRODUCTION (N5160)

SEC. 12 T.9S, R.17E

FIELD: EIGHT MILE FLAT NORTH (590)

COUNTY: UTAH

SPACING: R649-3-2 / GENERAL SITING



Utah Oil Gas and Mining

Wells

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL

Unit Status

- ☐ EXPLORATORY
- ☐ GAS STORAGE
- ☐ NF PP OIL
- ☐ NF SECONDARY
- ☐ PENDING
- ☐ PI OIL
- ☐ PP GAS
- ☐ PP GEOTHERML
- ☐ PP OIL
- ☐ SECONDARY
- ☐ TERMINATED

Field Status

- ☐ ABANDONED
- ☐ ACTIVE
- ☐ COMBINED
- ☐ INACTIVE
- ☐ PROPOSED
- ☐ STORAGE
- ☐ TERMINATED



PREPARED BY: DIANA MASON
DATE: 03-SEPTEMBER-2003



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

(801) 538-5340 telephone

(801) 359-3940 fax

(801) 538-7223 TTY

www.nr.utah.gov

Michael O. Leavitt
Governor

Robert L. Morgan
Executive Director

Lowell P. Braxton
Division Director

September 4, 2003

Inland Production Company
Route #3, Box 3630
Myton, UT 84052

Re: Federal 15-12-9-17 Well, 659' FSL, 1981' FEL, SW SE, Sec. 12, T. 9 South, R. 17 East,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-35169.

Sincerely,

A handwritten signature in black ink, appearing to read 'John R. Baza', written over the printed name and title.

John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Inland Production Company
Well Name & Number Federal 15-12-9-17
API Number: 43-047-35169
Lease: U-39713

Location: SW SE **Sec.** 12 **T.** 9 South **R.** 17 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

005

RECEIVED

JUL 19 2004

Form 3160-3
(September 2001)

DIV. OF OIL, GAS & MINING

FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: ☒ DRILL ☐ REENTER1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator

Inland Production Company

3a. Address

Route #3 Box 3630, Myton UT 84052

3b. Phone No. (include area code)

(435) 646-3721

4. Location of Well (Report location clearly and in accordance with any State requirements.)*

At surface SW/SE 659' FSL 1981' FEL

At proposed prod. zone

14. Distance in miles and direction from nearest town or post office*

Approximatley 17.0 miles southeast of Myton, Utah

15. Distance from proposed*
location to nearest
property or lease line, ft.

(Also to nearest drig. unit line, if any) Approx. 1981' f/lse, NA f/unit

18. Distance from proposed location*
to nearest well, drilling, completed,
applied for, on this lease, ft.

Approx. 2503'

16. No. of Acres in lease

1,120.00

19. Proposed Depth

6500'

17. Spacing Unit dedicated to this well

40 Acres

20. BLM/BIA Bond No. on file

#4488944

21. Elevations (Show whether DF, KDB, RT, GL, etc.)

5097' GR

22. Approximate date work will start*

4th Quarter 2003

23. Estimated duration

Approximately seven (7) days from spud to rig release.

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature

Mandie Crozier

Name (Printed/Typed)

Mandie Crozier

Date

8/29/03

Title

Regulatory Specialist

Approved by (Signature)

Howard R. Cleary

Name (Printed/Typed)

Howard R. Cleary

Date

07/12/2004

Title

Assistant Field Manager
Mineral Resources

Office

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

NOTICE OF APPROVAL

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

CONDITIONS OF APPROVAL ATTACHED

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Inland Production Company.

Well Name & Number: Federal 15-12-9-17

API Number 43-047-35169

Lease Number: U-39713

Location: SWSE Sec. 12 T.9S R. 17E

Agreement: N/A

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

**Please submit to this office, in LAS format, an electronic copy of all logs run on this well
This submission will replace the requirement for submittal of paper logs to the BLM.**

In the event after-hours approvals are necessary, you must contact one of the following individuals:

Ed Forsman (435) 828-7874
Petroleum Engineer

Kirk Fleetwood (435) 828-7875
Petroleum Engineer

BLM FAX Machine (435) 781-4410

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

-No construction or drilling shall be allowed during the burrowing owl nesting season (April 1 to Aug. 15), without first consulting the BLM biologist. If no nesting owls are found, drilling will be allowed.

-Mountain Plover surveys would have to be conducted in accordance with the U.S. Fish and Wildlife Service Mountain Plover Survey Guidelines.

-To reduce noise levels in the area, a hospital muffler or multi-cylinder engine shall be installed on the pumping unit.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

006

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

659 FSL 1981 FEL SW/SE Section 12, T9S R17E

5. Lease Designation and Serial No.

U-39713

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

N/A

8. Well Name and No.

FEDERAL 15-12-9-17

9. API Well No.

43-047-35169

10. Field and Pool, or Exploratory Area

EIGHT MILE FLAT

11. County or Parish, State

UINTAH COUNTY, UT.

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other **Permit Extension**

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Inland Production Company requests to extend the Permit to Drill this well for one year. The original approval date was 9/4/03 (expiration 9/4/04).

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 08-30-04

By: [Signature]

COPY SENT TO OPERATOR
Date: 8-31-04
Initials: CHD

RECEIVED
AUG 24 2004

14. I hereby certify that the foregoing is true and correct

Signed

Mandie Crozier
Mandie Crozier

Title

Regulatory Specialist

Date

DIV. OF OIL, GAS & MINING
8/27/04

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

CC: Utah DOGM

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-35169
Well Name: Federal 15-12-9-17
Location: SW/SE Section 12, T9S R17E
Company Permit Issued to: Inland Production Company
Date Original Permit Issued: 9/4/2003

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒ NA

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

8/27/2004

Date

Title: Regulatory Specialist

Representing: Inland Production Company



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>



IN REPLY REFER TO:
3106
(UT-924)

September 16, 2004

Memorandum

To: Vernal Field Office
From: Acting Chief, Branch of Fluid Minerals
Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard
Acting Chief, Branch of
Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare

UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	63073O	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357	76189X
05843	33992	65207	74398	77359	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560		



Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
INLAND PRODUCTION COMPANY

FILED
In the Office of the
Secretary of State of Texas
SEP 02 2004
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs
Susan G. Riggs, Treasurer

DIVISION OF OIL, GAS AND MINING***SPUDDING INFORMATION***Name of Company: INLAND PRODUCTION COMPANYWell Name: FEDERAL 15-12-9-17Api No: 43-047-35169 Lease Type: FEDERALSection 12 Township 09S Range 17E County UINTAHDrilling Contractor NDSI RIG # 1**SPUDDED:**Date 10/11/04Time 1:00 PMHow DRY***Drilling will commence:*** _____Reported by RAY HERRERATelephone # 1-435-823-1990Date 10/14/2004 Signed CHD

008

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

Operator: *Inland*
NEWFIELD PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3630
MYTON, UT 84052

OPERATOR ACCT. NO. *N5160* **N2695**

RECEIVED
OCT 14 2004

DIV. OF OIL, GAS & MINING

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RE	COUNTY		
A	99999	<i>14342</i>	43-013-32400	Ashley Federal 9-14-9-15	NE/SE	14	9S	15E	Duchesne	September 28, 2004	<i>10/19/04</i>
WELL 1 COMMENTS: <i>GRRU</i>											
A	99999	<i>14343</i>	43-047-35162	Federal 3-12-9-17	NE/NW	12	9S	17E	Uintah	October 4, 2004	<i>10/19/04</i>
WELL 2 COMMENTS: <i>GRRU</i>											
A	99999	<i>14344</i>	43-047-35164	Federal 5-12-9-17	SW/NW	12	9S	17E	Uintah	October 6, 2004	<i>10/19/04</i>
WELL 3 COMMENTS: <i>GRRU</i>											
A	99999	<i>14345</i>	43-047-35167	Federal 11-12-9-17	NE/SW	12	9S	17E	Uintah	October 7, 2004	<i>10/19/04</i>
WELL 4 COMMENTS: <i>GRRU</i>											
A	99999	<i>14346</i>	43-047-35169	Federal 15-12-9-17	SW/SE	12	9S	17E	Uintah	October 11, 2004	<i>10/19/04</i>
WELL 5 COMMENTS: <i>GRRU</i>											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Reassign well from one existing entity to another existing entity
- D - Reassign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

Kebble S. Jones
Signature
Kebble S. Jones
Production Clerk
October 14, 2004
Date

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

COP

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

009

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

659 FSL 1981 FEL

SW/SE Section 12 T9S R17E

5. Lease Serial No.

UTU39713

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

FEDERAL 15-12-9-17

9. API Well No.

4304735169

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Spud Notice _____
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	_____

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 10/11/04 MIRU NDSI NS # 1. Spud well @ 1:00 PM. Drill 335' of 12 1/4" hole with air mist. TIH W/ 8 Jt's 8 5/8" J-55 24 # csgn. Set @ 327' KB On 10-14-04 cement with 150 sks of class "G" w/ 3% CaCL2 + 1/4# sk Cello- Flake Mixed @ 15.8 ppg > 1.17 cf/ sk yeild. Returned 5 bbls cement to pit. WOC.

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)
Floyd Mitchell

Title

Drilling Supervisor

Signature

Date

10/15/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

RECEIVED

OCT 19 2004

DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8 CASING SET AT 327.71

LAST CASING 8 5/8" SET AT 327.71'
 DATUM 12. KB
 DATUM TO CUT OFF CASING _____
 DATUM TO BRADENHEAD FLANGE _____
 TD DRILLER 300 LOGGER _____
 HOLE SIZE 12 1/4

OPERATOR Newfield Production Company
 WELL Federal 15-12-9-17
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # NDSI NS #1

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		35.58' sh jt' shjt					
		WHI - 92 csg head			8rd	A	0.95
8	8 5/8"	Maverick ST&C csg	24#	J-55	8rd	A	315.86
		GUIDE shoe			8rd	A	0.9

CASING INVENTORY BAL.	FEET	JTS	TOTAL LENGTH OF STRING	317.71
TOTAL LENGTH OF STRING	317.71	8	LESS CUT OFF PIECE	2
LESS NON CSG. ITEMS	1.85		PLUS DATUM TO T/CUT OFF CSG	12
PLUS FULL JTS. LEFT OUT	0		CASING SET DEPTH	327.71
TOTAL	315.86	8	} COMPARE	
TOTAL CSG. DEL. (W/O THRDS)	315.86	8		
TIMING	1ST STAGE		GOOD CIRC THRU JOB	Yes
BEGIN RUN CSG. Spud	10/11/2004	1:00 PM	Bbls CMT CIRC TO SURFACE	5
CSG. IN HOLE	10/12/2004	1:00 PM	RECIPROCATED PIPE FOR	THRU FT STROKE
BEGIN CIRC	10/14/2004	3:30 PM	DID BACK PRES. VALVE HOLD ?	N/A
BEGIN PUMP CMT	10/14/2004	3:38 PM	BUMPED PLUG TO	319 PSI
BEGIN DSPL. CMT	10/14/2004		3:58 PM	
PLUG DOWN	Cemented	10/14/2004		

CEMENT USED		CEMENT COMPANY- B. J.
STAGE	# SX	CEMENT TYPE & ADDITIVES
1	150	Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield
CENTRALIZER & SCRATCHER PLACEMENT		SHOW MAKE & SPACING
Centralizers - Middle first, top second & third for 3		

COMPANY REPRESENTATIVE Floyd Mitchell DATE 10/15/2004

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

DEC 30 2004
DIV. OF OIL, GAS & MINING

FORM APPROVED
OMB No. 1004-0117
Expires January 31, 2004

COPY

011

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include are code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

659 FSL 1981 FEL

SW/SE Section 12 T9S R17E

5. Lease Serial No.

UTU39713

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

FEDERAL 15-12-9-17

9. API Well No.

4304735169

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Weekly Status Report
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomple in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Status report for time period 12/16/04 – 12/28/04

Subject well had completion procedures initiated in the Green River formation on 12/16/04 without the use of a service rig over the well. A cement bond log was run and a total of five Green River intervals were perforated and hydraulically fracture treated w/ 20/40 mesh sand. Perf intervals were #1 (5597-5601'), (5562-5580') (ALL 4 JSPF); #2 (5408-5413'), (5395-5399') (ALL 4 JSPF); #3 (4940-4946') (4 JSPF); #4 (4780-4786'), (4735-4741') (ALL 4 JSPF); #5 (4066-4076'), (4047-4062') (ALL 4 JSPF). Composite flow-through frac plugs were used between stages. Fracs were flowed back through chokes. A service rig was moved on well on 12/23/04. Bridge plugs were drilled out. Well was cleaned out to PBTD @ 5711'. Zones were swab tested for sand cleanup. A BHA & production tbg string were run in and anchored in well. End of tubing string @ 5625.98'. A new 1 1/2" bore rod pump was run in well on sucker rods. Well was placed on production via rod pump on 12/28/04.

RECEIVED

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)
Renee Palmer

Title

Production Clerk

Signature

Date

12/29/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

NEWFIELD



January 26, 2005

State of Utah, Division of Oil, Gas and Mining
Attn: Ms. Carol Daniels
P.O. Box 145801
Salt Lake City, Utah 84114-5801

Attn: Ms. Carol Daniels

Federal 15-12-9-17 (4304735169)

Dear Ms. Carol Daniels

Enclosed is a Well Completion or Recompletion Report and Log form (Form 3160-4). We are no longer sending Log copies since Pat Grissom of Phoenix Surveys is already doing so.

If you should have any questions, please contact me at (303) 382-4449.

Sincerely,

Brian Harris
Engineering Tech

Enclosures

cc: Bureau of Land Management
Vernal District Office, Division of Minerals
Attn: Edwin I. Forsman
170 South 500 East
Vernal, Utah 84078

Well File – Denver
Well File – Roosevelt
Patsy Barreau/Denver
Bob Jewett/Denver
Renee Palmer/Roosevelt

RECEIVED

JAN 28 2005

DIV. OF OIL, GAS & MINING

012

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WORK

OIL
WELL ☒GAS
WELL ☐DRY ☐

Other _____

1b. TYPE OF WELL

NEW
WELL ☒WORK
OVER ☐DEEPEN ☐PLUG
BACK ☐DIFF
RESVR. ☐

Other _____

2. NAME OF OPERATOR

Newfield Exploration Company

3. ADDRESS AND TELEPHONE NO.

1401 17th St. Suite 1000 Denver, CO 80202

4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.)*

At Surface

659' FSL & 1981' FEL (SW SE) Sec. 12, Twp 9S, Rng 17E

At top prod. Interval reported below

At total depth

14. API NO.

43-047-35169

DATE ISSUED

9/4/2003

12. COUNTY OR PARISH

Utah

13. STATE

UT

15. DATE SPUDDED

10/11/2004

16. DATE T.D. REACHED

12/2/2004

17. DATE COMPL. (Ready to prod.)

12/28/2004

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*

5097' GL

19. ELEV. CASINGHEAD

5109' KB

20. TOTAL DEPTH, MD & TVD

5767'

21. PLUG BACK T.D., MD & TVD

5711'

22. IF MULTIPLE COMPL.,
HOW MANY*23. INTERVALS
DRILLED BY

----->

ROTARY TOOLS

X

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)*

Green River 4047'-5601'

25. WAS DIRECTIONAL
SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log

27. WAS WELL CORED

No

23. CASING RECORD (Report all strings set in well)

CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENTING RECORD	AMOUNT PULLED
8-5/8" - J-55	24#	328'	12-1/4"	To surface with 150 sx Class "G" cmt	
5-1/2" - J-55	15.5#	5753'	7-7/8"	285 sx Premlite II and 400 sx 50/50 Poz	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-7/8"	EOT @ 5626'	TA @ 5525'

31. PERFORATION RECORD (Interval, size and number)

INTERVAL	SIZE	SPF/NUMBER	DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
(CP4,5) 5562-80', 5597-5601'	.41"	4/88	5562'-5601'	Frac w/ 40,225# 20/40 sand in 422 bbls fluid.
(CP 2) 5395-99', 5408-13'	.41"	4/36	5395'-5413'	Frac w/ 29,582# 20/40 sand in 353 bbls fluid.
(A1) 4940'-4946'	.41"	4/24	4940'-4946'	Frac w/ 14,813# 20/40 sand in 229 bbls fluid.
(B.5,1) 4735-41', 4780-86'	.41"	4/48	4735'-4786'	Frac w/ 48,957# 20/40 sand in 420 bbls fluid.
(GB6) 4047-62', 4066-76'	.41"	4/100	4047'-4076'	Frac w/ 69,613# 20/40 sand in 532 bbls fluid.

33.* PRODUCTION

DATE FIRST PRODUCTION 12/28/2004		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) 2-1/2" x 1-1/2" x 15' RHAC Pump					WELL STATUS (Producing or shut-in) PRODUCING	
DATE OF TEST 10 day ave	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD ----->	OIL--BBL. 84	GAS--MCF. 90	WATER--BBL. 8		GAS-OIL RATIO 1071
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE ----->	OIL--BBL.	GAS--MCF.	WATER--BBL.		OIL GRAVITY-API (CORR.)	
RECEIVED								

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold & Used for Fuel

TEST WITNESSED BY

JAN 28 2005

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

Brian Harris

TITLE

Engineering Technician

DATE

1/26/2005

BDH

*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
			Well Name Federal 15-12-9-17		MEAS. DEPTH	TRUE VERT. DEPTH
				Garden Gulch Mkr	3533'	
				Garden Gulch 1	3709'	
				Garden Gulch 2	3822'	
				Point 3 Mkr		
				X Mkr	4308'	
				Y-Mkr	4353'	
				Douglas Creek Mkr	4482'	
				BiCarbonate Mkr	4811'	
				B Limestone Mkr		
				Castle Peak	5294'	
				Basal Carbonate		
				Total Depth (LOGGERS	5770'	

OPERATOR CHANGE WORKSHEET

013

Change of Operator (Well Sold)

Designation of Agent/Operator

ROUTING

1. GLH

2. CDW

3. FILE

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

9/1/2004

FROM: (Old Operator):

N5160-Inland Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

TO: (New Operator):

N2695-Newfield Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

CA No.

Unit:

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	
FEDERAL 10-1-9-17	01	090S	170E	4304735090	14421	Federal	OW	DRL	K
FEDERAL 9-1-9-17	01	090S	170E	4304735179	14075	Federal	OW	P	K
FEDERAL 11-1-9-17	01	090S	170E	4304735180	14105	Federal	OW	P	K
FEDERAL 1-11-9-17	11	090S	170E	4304735156	14321	Federal	OW	P	K
FEDERAL 7-11-9-17	11	090S	170E	4304735157	14249	Federal	OW	P	K
FEDERAL 9-11-9-17	11	090S	170E	4304735158	14250	Federal	OW	P	K
FEDERAL 11-11-9-17	11	090S	170E	4304735159	14287	Federal	OW	P	K
FEDERAL 15-11-9-17	11	090S	170E	4304735160	14302	Federal	OW	P	K
FEDERAL 3-12-9-17	12	090S	170E	4304735162	14343	Federal	OW	P	K
FEDERAL 1-12-9-17	12	090S	170E	4304735163	14361	Federal	OW	DRL	K
FEDERAL 5-12-9-17	12	090S	170E	4304735164	14344	Federal	OW	P	K
FEDERAL 7-12-9-17	12	090S	170E	4304735165	14347	Federal	OW	P	K
FEDERAL 9-12-9-17	12	090S	170E	4304735166	14391	Federal	OW	DRL	K
FEDERAL 11-12-9-17	12	090S	170E	4304735167	14345	Federal	OW	P	K
FEDERAL 13-12-9-17	12	090S	170E	4304735168	14305	Federal	OW	P	K
FEDERAL 15-12-9-17	12	090S	170E	4304735169	14346	Federal	OW	P	K
FEDERAL 2-25-9-17	25	090S	170E	4304734951		Federal	OW	APD	K
FEDERAL 3-14-9-18	14	090S	180E	4304734943		Federal	OW	APD	K
FEDERAL 4-14-9-18	14	090S	180E	4304734944		Federal	OW	APD	K
FEDERAL 2-23-9-18	23	090S	180E	4304734950		Federal	OW	APD	K

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/15/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/15/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/23/2005

4. Is the new operator registered in the State of Utah: YES Business Number: 755627-0143

5. If NO, the operator was contacted contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 2/28/2005
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919
2. The **FORMER** operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

June 30, 2005

Newfield Production Company
Attn: Kelly L. Donohoue
1401 Seventeenth Street, Suite 1000
Denver, Colorado 80202

Gentlemen:

The Sundance (Green River) Unit Agreement, Uintah County, Utah, was approved June 30, 2005. This agreement has been designated No. UTU82472X, and is effective July 1, 2005. The unit area embraces 11,143.86 acres, more or less.

Pursuant to regulations issued and effective June 17, 1988, all operations within the Sundance (Green River) Unit will be covered by your nationwide (Utah) oil and gas bond No. 0056.

The following leases embrace lands included within the unit area:

UTU0075174	UTU39713	UTU65970*	UTU79013*
UTU16539*	UTU39714	UTU74404	UTU79014*
UTU16540	UTU44429	UTU74835	UTU80915
UTU17424*	UTU64806*	UTU74872*	UTU82205
UTU18043	UTU65969	UTU75234	

* Indicates lease to be considered for segregation by the Bureau of Land Management pursuant to Section 18 (g) of the unit agreement and Public Law 86-705.

All lands and interests by State of Utah, Cause No. 228-08 are fully committed.

Approval of this agreement does not warrant or certify that the operator thereof and other holders of operating rights hold legal or equitable title to those rights in the subject leases which are committed hereto.

RECEIVED

JUL 0 / 2005

DIV. OF OIL, GAS & MINING

*Docket No
2005-009*

We are of the opinion that the agreement is necessary and advisable in the public interest and for the purpose of more properly conserving natural resources. Certification-Determination, signed by the School and Institutional Trust Land Administration for the State of Utah, is attached to the enclosed agreement. We request that you furnish the State of Utah and all other interested principals with appropriate evidence of this approval.

Sincerely,

/s/ Terry Catlin

Terry Catlin
Acting Chief, Branch of Fluid Minerals

Enclosure

bcc: Mary Higgins w/enclosure
MMS - Data Management Division (Attn: James Sykes)
Trust Lands Administration
Division of Oil, Gas and Mining
Field Manager - Vernal w/enclosure
File - Sundance (Green River) Unit w/enclosure
Agr. Sec. Chron
Fluid Chron
Central Files

UT922:TAThompson:tt:06/30/2005

Entity Form 6
"C" Change from one existing entity to another existing entity

API	Well	Sec	Twsp	Rng	Entity	Entity Eff Date
4304734465	SUNDANCE 15-32-8-18	32	080S	180E	13978 to 14844	9/20/2005
4304734466	SUNDANCE 16-32-8-18	32	080S	180E	14028 to 14844	9/20/2005
4304735090	FEDERAL 10-1-9-17	01	090S	170E	14421 to 14844	9/20/2005
4304735179	FEDERAL 9-1-9-17	01	090S	170E	14075 to 14844	9/20/2005
4304735180	FEDERAL 11-1-9-17	01	090S	170E	14105 to 14844	9/20/2005
4304735181	FEDERAL 13-1-9-17	01	090S	170E	14101 to 14844	9/20/2005
4304735182	FEDERAL 15-1-9-17	01	090S	170E	14094 to 14844	9/20/2005
4304735496	FEDERAL 16-1-9-17	01	090S	170E	14481 to 14844	9/20/2005
4304735156	FEDERAL 1-11-9-17	11	090S	170E	14321 to 14844	9/20/2005
4304735157	FEDERAL 7-11-9-17	11	090S	170E	14249 to 14844	9/20/2005
4304735158	FEDERAL 9-11-9-17	11	090S	170E	14250 to 14844	9/20/2005
4304735159	FEDERAL 11-11-9-17	11	090S	170E	14287 to 14844	9/20/2005
4304735160	FEDERAL 15-11-9-17	11	090S	170E	14302 to 14844	9/20/2005
4304735295	FEDERAL 3-11-9-17	11	090S	170E	14258 to 14844	9/20/2005
4304735497	FEDERAL 16-11-9-17	11	090S	170E	14568 to 14844	9/20/2005
4304735498	FEDERAL 14-11-9-17	11	090S	170E	14621 to 14844	9/20/2005
4304735500	FEDERAL 10-11-9-17	11	090S	170E	14587 to 14844	9/20/2005
4304735501	FEDERAL 8-11-9-17	11	090S	170E	14578 to 14844	9/20/2005
4304735502	FEDERAL 2-11-9-17	11	090S	170E	14588 to 14844	9/20/2005
4304735769	FEDERAL 6-11-9-17	11	090S	170E	14595 to 14844	9/20/2005
4304735162	FEDERAL 3-12-9-17	12	090S	170E	14343 to 14844	9/20/2005
4304735163	FEDERAL 1-12-9-17	12	090S	170E	14361 to 14844	9/20/2005
4304735164	FEDERAL 5-12-9-17	12	090S	170E	14344 to 14844	9/20/2005
4304735165	FEDERAL 7-12-9-17	12	090S	170E	14347 to 14844	9/20/2005
4304735166	FEDERAL 9-12-9-17	12	090S	170E	14391 to 14844	9/20/2005
4304735167	FEDERAL 11-12-9-17	12	090S	170E	14345 to 14844	9/20/2005
4304735168	FEDERAL 13-12-9-17	12	090S	170E	14305 to 14844	9/20/2005
4304735169	FEDERAL 15-12-9-17	12	090S	170E	14346 to 14844	9/20/2005
4304735516	FEDERAL 16-12-9-17	12	090S	170E	14569 to 14844	9/20/2005
4304735517	FEDERAL 14-12-9-17	12	090S	170E	14500 to 14844	9/20/2005
4304735518	FEDERAL 12-12-9-17	12	090S	170E	14497 to 14844	9/20/2005
4304735519	FEDERAL 10-12-9-17	12	090S	170E	14482 to 14844	9/20/2005
4304735520	FEDERAL 4-12-9-17	12	090S	170E	14553 to 14844	9/20/2005
4304735748	FEDERAL 8-12-9-17	12	090S	170E	14483 to 14844	9/20/2005
4304735749	FEDERAL 6-12-9-17	12	090S	170E	14498 to 14844	9/20/2005
4304735750	FEDERAL 2-12-9-17	12	090S	170E	14484 to 14844	9/20/2005



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8

999 18th STREET - SUITE 300
DENVER, CO 80202-2466
<http://www.epa.gov/region08>

SEP 21 2006

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

David Gerbig
Newfield Production Company
1401 Seventeenth Street
Suite 1000
Denver, CO 80202

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

43.047.35169
95 17E 12

Re: Underground Injection Control Program
Final Permit: Federal 15-12-9-17 Well
Uintah County, Utah
EPA Permit No. UT21029-06982

Dear Mr. Gerbig:

Enclosed is your copy of the FINAL Underground Injection Control (UIC) Permit for the proposed Federal 15-12-9-17 injection well. A Statement of Basis, which discusses development of the conditions and requirements of the Permit, also is included.

The Public Comment period ended on SEP 21 2006. There were no comments on the Draft Permit received during the Public Notice period, and therefore the Final Permit becomes effective on the date of issuance. All conditions set forth herein refer to Title 40 Parts 124, 144, 146, and 147 of the Code of Federal Regulations (CFR) and are regulations that are in effect on the date that this Permit becomes effective.

Please note that under the terms of the Final Permit, you are authorized only to construct the proposed injection well, and must fulfill the "Prior to Commencing Injection" requirements of the Permit, Part II Section C Subpart 1 and obtain written Authorization to Inject prior to commencing injection. It is your responsibility to be familiar with and to comply with all provisions of the Final Permit.

The Permit and the authorization to inject are issued for the operating life of the well unless terminated (Part III, Section B). The EPA will review this Permit at least every five (5) years to determine whether action under 40 CFR § 144.36(a) is warranted.

RECEIVED


OCT 02 2006



DIV. OF OIL, GAS & MINING
Printed on Recycled Paper

If you have any questions on the enclosed Final Permit or Statement of Basis, please call Emmett Schmitz of my staff at (303) 312-6174, or toll-free at (800) 227-8917, ext. 6174.

Sincerely,



for Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

enclosure: Final UIC Permit
Statement of Basis
Form 7520-7 Application to Transfer Permit
Form 7520-10 Completion Report
Form 7520-11 Monitoring Report
Form 7520-12 Well Rework Record
Form 7520-13 Plugging Record
Groundwater Section Guidance 35
Groundwater Section Guidance 37
Groundwater Section Guidance 39

cc: Letter only:

Maxine Natchees
Acting Chairperson
Uintah & Ouray Business Committee
Ute Indian Tribe

Chester Mills
Superintendent
U.S. Bureau of Indian Affairs
Uintah & Ouray Indian Agency

Final Permit & Statement of Basis:

S. Elaine Willie
Environmental Coordinator
Ute Indian Tribe



Lynn Becker
Director
Energy & Minerals Dept.
Ute Indian Tribe

Gilbert Hunt
Associate Director
State of Utah - Natural Resources

Fluid Minerals Engineerring Office
U.S. Bureau of Land Management
Vernal, Utah

all enclosures:

Michael Guinn
Vice President - Operations
Newfield Production Company
Myton, Utah





**UNDERGROUND INJECTION CONTROL PROGRAM
PERMIT**

PREPARED: September 2006

Permit No. UT21029-06982

Class II Enhanced Oil Recovery Injection Well

**Federal 15-12-9-17
Uintah County, UT**

Issued To

Newfield Production Company

1401 Seventeenth Street
Suite 1000
Denver, CO 80202

RECEIVED

OCT 02 2006

DIV. OF OIL, GAS & MINING

Part I. AUTHORIZATION TO CONSTRUCT AND OPERATE

Under the authority of the Safe Drinking Water Act and Underground Injection Control (UIC) Program regulations of the U. S. Environmental Protection Agency (EPA) codified at Title 40 of the Code of Federal Regulations (40 CFR) Parts 2, 124, 144, 146, and 147, and according to the terms of this Permit,

Newfield Production Company
1401 Seventeenth Street
Suite 1000
Denver, CO 80202

is authorized to construct and to operate the following Class II injection well or wells:

Federal 15-12-9-17
659' FSL & 1981' FEL, SWSE S12, T9S, R17E
Uintah County, UT


Permit requirements herein are based on regulations found in 40 CFR Parts 124, 144, 146, and 147 which are in effect on the Effective Date of this Permit. Issuance of this Permit does not convey any property rights of any sort, nor does it authorize any injury to persons or property or invasion of other private rights, or any infringement of other federal, State or local law or regulation.

This Permit is based on representations made by the applicant and on other information contained in the Administrative Record. Misrepresentation of information or failure to fully disclose all relevant information may be cause for termination, revocation and reissuance, or modification of this Permit and/or formal enforcement action. This Permit will be reviewed periodically to determine whether action under 40 CFR 144.36(a) is required.

This Permit is issued for the life of the well or wells unless modified, revoked and reissued, or terminated under 40 CFR 144.39 or 144.40. This Permit may be adopted, modified, revoked and reissued, or terminated if primary enforcement authority for this program is delegated to an Indian Tribe or a State. Upon the effective date of delegation, all reports, notifications, questions and other compliance actions shall be directed to the Indian tribe or State Program Director or designee.

Issue Date: SEP 21 2006

Effective Date SEP 21 2006


for Stephen S. Tuber
Assistant Regional Administrator*
Office of Partnerships and Regulatory Assistance

*NOTE: The person holding this title is referred to as the "Director" throughout this Permit.

PART II. SPECIFIC PERMIT CONDITIONS

Section A. WELL CONSTRUCTION REQUIREMENTS

These requirements represent the approved minimum construction standards for well casing and cement, injection tubing, and packer.

Details of the approved well construction plan are incorporated into this Permit as APPENDIX A. Changes to the approved plan that may occur during construction must be approved by the Director prior to being physically incorporated.

1. Casing and Cement.

The well or wells shall be cased and cemented to prevent the movement of fluids into or between underground sources of drinking water. The well casing and cement shall be designed for the life expectancy of the well and of the grade and size shown in APPENDIX A. Remedial cementing may be required if shown to be inadequate by cement bond log or other attempted demonstration of Part II (External) mechanical integrity.

2. Injection Tubing and Packer.

Injection tubing is required, and shall be run and set with a packer at or below the depth indicated in APPENDIX A. The packer setting depth may be changed provided it remains below the depth indicated in APPENDIX A and the Permittee provides notice and obtains the Director's approval for the change.

3. Sampling and Monitoring Devices.

The Permittee shall install and maintain in good operating condition:

- (a) a "tap" at a conveniently accessible location on the injection flow line between the pump house or storage tanks and the injection well, isolated by shut-off valves, for collection of representative samples of the injected fluid; and
- (b) one-half (1/2) inch female iron pipe fitting, isolated by shut-off valves and located at the wellhead at a conveniently accessible location, for the attachment of a pressure gauge capable of monitoring pressures ranging from normal operating pressures up to the Maximum Allowable Injection Pressure specified in APPENDIX C:
 - (i) on the injection tubing; and
 - (ii) on the tubing-casing annulus (TCA); and
- (c) a pressure actuated shut-off device attached to the injection flow line set to shut-off the injection pump when or before the Maximum Allowable Injection Pressure specified in APPENDIX C is reached at the wellhead; and
- (d) a non-resettable cumulative volume recorder attached to the injection line.

4. Well Logging and Testing

Well logging and testing requirements are found in APPENDIX B. The Permittee shall ensure the log and test requirements are performed within the time frames specified in APPENDIX B. Well logs and tests shall be performed according to current EPA-approved procedures. Well log and test results shall be submitted to the Director within sixty (60) days of completion of the logging or testing activity, and shall include a report describing the methods used during logging or testing and an interpretation of the test or log results.

5. Postponement of Construction or Conversion

The Permittee shall complete well construction within one year of the Effective Date of the Permit, or in the case of an Area Permit within one year of authorization of the additional well. Authorization to construct and operate shall expire if the well has not been constructed within one year of the Effective Date of the Permit or authorization and the Permit may be terminated under 40 CFR 144.40, unless the Permittee has notified the Director and requested an extension prior to expiration. Notification shall be in writing, and shall state the reasons for the delay and provide an estimated completion date. Once Authorization has expired under this part, the complete permit process including opportunity for public comment may be required before Authorization to construct and operate may be reissued.

6. Workovers and Alterations

Workovers and alterations shall meet all conditions of the Permit. Prior to beginning any addition or physical alteration to an injection well that may significantly affect the tubing, packer or casing, the Permittee shall give advance notice to the Director and obtain the Director's approval. The Permittee shall record all changes to well construction on a Well Rework Record (EPA Form 7520-12), and shall provide this and any other record of well workover, logging, or test data to EPA within sixty (60) days of completion of the activity.

A successful demonstration of Part I MI is required following the completion of any well workover or alteration which affects the casing, tubing, or packer. Injection operations shall not be resumed until the well has successfully demonstrated mechanical integrity and the Director has provided written approval to resume injection.

Section B. MECHANICAL INTEGRITY

The Permittee is required to ensure each injection well maintains mechanical integrity at all times. The Director, by written notice, may require the Permittee to comply with a schedule describing when mechanical integrity demonstrations shall be made.

An injection well has mechanical integrity if:

- (a) There is no significant leak in the casing, tubing, or packer (Part I); and
- (b) There is no significant fluid movement into an underground source of drinking water through vertical channels adjacent to the injection well bore (Part II).

1. Demonstration of Mechanical Integrity (MI).

The operator shall demonstrate MI prior to commencing injection and periodically thereafter. Well-specific conditions dictate the methods and the frequency for demonstrating MI and are discussed in the Statement of Basis. The logs and tests are designed to demonstrate both internal (Part I) and external (Part II) MI as described above. The conditions present at this well site warrant the methods and frequency required in Appendix B of this Permit.

In addition to these regularly scheduled demonstrations of MI, the operator shall demonstrate internal (Part I) MI after any workover which affects the tubing, packer or casing.

The Director may require additional or alternative tests if the results presented by the operator are not satisfactory to the Director to demonstrate there is no movement of fluid into or between USDWs resulting from injection activity. Results of MI tests shall be submitted to the Director as soon as possible but no later than sixty (60) days after the test is complete.

2. Mechanical Integrity Test Methods and Criteria

EPA-approved methods shall be used to demonstrate mechanical integrity. Ground Water Section Guidance No. 34 "Cement Bond Logging Techniques and Interpretation", Ground Water Section Guidance No. 37, "Demonstrating Part II (External) Mechanical Integrity for a Class II injection well permit", and Ground Water Section Guidance No. 39, "Pressure Testing Injection Wells for Part I (Internal) Mechanical Integrity" are available from EPA and will be provided upon request.

The Director may stipulate specific test methods and criteria best suited for a specific well construction and injection operation.

3. Notification Prior to Testing.

The Permittee shall notify the Director at least 30 days prior to any scheduled mechanical integrity test. The Director may allow a shorter notification period if it would be sufficient to enable EPA to witness the mechanical integrity test. Notification may be in the form of a yearly or quarterly schedule of planned mechanical integrity tests, or it may be on an individual basis.

4. Loss of Mechanical Integrity.

If the well fails to demonstrate mechanical integrity during a test, or a loss of mechanical integrity becomes evident during operation (such as presence of pressure in the TCA, water flowing at the surface, etc.), the Permittee shall notify the Director within 24 hours (see Part III Section E Paragraph 11(e) of this Permit) and the well shall be shut-in within 48 hours unless the Director requires immediate shut-in.

Within five days, the Permittee shall submit a follow-up written report that documents test results, repairs undertaken or a proposed remedial action plan.

Injection operations shall not be resumed until after the well has successfully been repaired and demonstrated mechanical integrity, and the Director has provided approval to resume injection.

Section C. WELL OPERATION

INJECTION BETWEEN THE OUTERMOST CASING PROTECTING UNDERGROUND SOURCES OF DRINKING WATER AND THE WELL BORE IS PROHIBITED.

Injection is approved under the following conditions:

1. Requirements Prior to Commencing Injection.

Well injection, including for new wells authorized by an Area Permit under 40 CFR 144.33 (c), may commence only after all well construction and pre-injection requirements herein have been met and approved. The Permittee may not commence injection until construction is complete, and

- (a) The Permittee has submitted to the Director a notice of completion of construction and a completed EPA Form 7520-10 or 7520-12; all applicable logging and testing requirements of this Permit (see APPENDIX B) have been fulfilled and the records submitted to the Director; mechanical integrity pursuant to 40 CFR 146.8 and Part II Section B of this Permit has been demonstrated; and
 - (i) The Director has inspected or otherwise reviewed the new injection well and finds it is in compliance with the conditions of the Permit; or
 - (ii) The Permittee has not received notice from the Director of his or her intent to inspect or otherwise review the new injection well within 13 days of the date of the notice in Paragraph 1a, in which case prior inspection or review is waived and the Permittee may commence injection.

2. Injection Interval.

Injection is permitted only within the approved injection interval, listed in APPENDIX C. Additional individual injection perforations may be added provided that they remain within the approved injection interval and the Permittee provides notice to the Director in accordance with Part II, Section A, Paragraph 6.

3. Injection Pressure Limitation

- (a) The permitted Maximum Allowable Injection Pressure (MAIP), measured at the wellhead, is found in APPENDIX C. Injection pressure shall not exceed the amount the Director determines is appropriate to ensure that injection does not initiate new fractures or propagate existing fractures in the confining zone adjacent to USDWs. In no case shall injection pressure cause the movement of injection or formation fluids into a USDW.
- (b) The Permittee may request a change of the MAIP, or the MAIP may be increased or decreased by the Director in order to ensure that the requirements in Paragraph (a) above are fulfilled. The Permittee may be required to conduct a step rate injection test or other suitable test to provide information for determining the fracture pressure of the injection zone. Change of the permitted MAIP by the Director shall be by modification of this Permit and APPENDIX C.

4. Injection Volume Limitation.

Injection volume is limited to the total volume specified in APPENDIX C.

5. Injection Fluid Limitation.

Injected fluids are limited to those identified in 40 CFR 144.6(b)(2) as fluids used for enhanced recovery of oil or natural gas, including those which are brought to the surface in connection with conventional oil or natural gas production that may be commingled with waste waters from gas plants which are an integral part of production operations unless those waters are classified as a hazardous waste at the time of injection, pursuant to 40 CFR 144.6(b). Non-exempt wastes, including unused fracturing fluids or acids, gas plant cooling tower cleaning wastes, service wastes and vacuum truck wastes, are NOT approved for injection. This well is NOT approved for commercial brine injection, industrial waste fluid disposal or injection of hazardous waste as defined by CFR 40 Part 261. The Permittee shall provide a listing of the sources of injected fluids in accordance with the reporting requirements in Part II Section D Paragraph 4 and APPENDIX D of this Permit.

6. Tubing-Casing Annulus (TCA)

The tubing-casing annulus (TCA) shall be filled with water treated with a corrosion inhibitor, or other fluid approved by the Director. The TCA valve shall remain closed during normal operating conditions and the TCA pressure shall be maintained at zero (0) psi.

If TCA pressure cannot be maintained at zero (0) psi, the Permittee shall follow the procedures in Ground Water Section Guidance No. 35 "Procedures to follow when excessive annular pressure is observed on a well."

Section D. MONITORING, RECORDKEEPING, AND REPORTING OF RESULTS

1. Monitoring Parameters, Frequency, Records and Reports.

Monitoring parameters are specified in APPENDIX D. Pressure monitoring recordings shall be taken at the wellhead. The listed parameters are to be monitored, recorded and reported at the frequency indicated in APPENDIX D even during periods when the well is not operating.

Monitoring records must include:

- (a) the date, time, exact place and the results of the observation, sampling, measurement, or analysis, and;
- (b) the name of the individual(s) who performed the observation, sampling, measurement, or analysis, and;
- (c) the analytical techniques or methods used for analysis.

2. Monitoring Methods.

- (a) Monitoring observations, measurements, samples, etc. taken for the purpose of complying with these requirements shall be representative of the activity or condition being monitored.

- (b) Methods used to monitor the nature of the injected fluids must comply with analytical methods cited and described in Table 1 of 40 CFR 136.3 or Appendix III of 40 CFR 261, or by other methods that have been approved in writing by the Director.
- (c) Injection pressure, annulus pressure, injection rate, and cumulative injected volumes shall be observed and recorded at the wellhead under normal operating conditions, and all parameters shall be observed simultaneously to provide a clear depiction of well operation.
- (d) Pressures are to be measured in pounds per square inch (psi).
- (e) Fluid volumes are to be measured in standard oil field barrels (bbl).
- (f) Fluid rates are to be measured in barrels per day (bbl/day).

3. Records Retention.

- (a) Records of calibration and maintenance, and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this permit, and records of all data used to complete the application for this permit shall be retained for a period of AT LEAST THREE (3) YEARS from the date of the sample, measurement, report, or application. This period may be extended anytime prior to its expiration by request of the Director.
- (b) Records of the nature and composition of all injected fluids must be retained until three (3) years after the completion of any plugging and abandonment (P&A) procedures specified under 40 CFR 144.52(a)(6) or under Part 146 Subpart G, as appropriate. The Director may require the Permittee to deliver the records to the Director at the conclusion of the retention period. The Permittee shall continue to retain the records after the three (3) year retention period unless the Permittee delivers the records to the Director or obtains written approval from the Director to discard the records.
- (c) The Permittee shall retain records at the location designated in APPENDIX D.

4. Annual Reports.

Whether the well is operating or not, the Permittee shall submit an Annual Report to the Director that summarizes the results of the monitoring required by Part II Section D and APPENDIX D.

The first Annual Report shall cover the period from the effective date of the Permit through December 31 of that year. Subsequent Annual Reports shall cover the period from January 1 through December 31 of the reporting year. Annual Reports shall be submitted by February 15 of the year following data collection. EPA Form 7520-11 may be copied and shall be used to submit the Annual Report, however, the monitoring requirements specified in this Permit are mandatory even if EPA Form 7520-11 indicates otherwise.

Section E. PLUGGING AND ABANDONMENT

1. Notification of Well Abandonment, Conversion or Closure.

The Permittee shall notify the Director in writing at least forty-five (45) days prior to: 1) plugging and abandoning an injection well, 2) converting to a non-injection well, and 3) in the case of an Area Permit, before closure of the project.

2. Well Plugging Requirements

Prior to abandonment, the injection well shall be plugged with cement in a manner which prevents the movement of fluids into or between underground sources of drinking water. Prior to placement of the cement plug(s) the well shall be in a state of static equilibrium with the mud weight equalized top to bottom, either by circulating the mud in the well at least once or by a comparable method prescribed by the Director. The well shall be plugged in accordance with the approved plugging and abandonment plan and with 40 CFR 146.10.

3. Approved Plugging and Abandonment Plan.

The approved plugging and abandonment plan is incorporated into this Permit as APPENDIX E. Changes to the approved plugging and abandonment plan must be approved by the Director prior to beginning plugging operations. The Director also may require revision of the approved plugging and abandonment plan at any time prior to plugging the well.

4. Forty Five (45) Day Notice of Plugging and Abandonment.

The Permittee shall notify the Director at least forty-five (45) days prior to plugging and abandoning a well and provide notice of any anticipated change to the approved plugging and abandonment plan.

5. Plugging and Abandonment Report.

Within sixty (60) days after plugging a well, the Permittee shall submit a report (EPA Form 7520-13) to the Director. The plugging report shall be certified as accurate by the person who performed the plugging operation. Such report shall consist of either:

- (a) A statement that the well was plugged in accordance with the approved plugging and abandonment plan; or
- (b) Where actual plugging differed from the approved plugging and abandonment plan, an updated version of the plan, on the form supplied by the Director, specifying the differences.

6. Inactive Wells.

After any period of two years during which there is no injection the Permittee shall plug and abandon the well in accordance with Part II Section E Paragraph 2 of this Permit unless the Permittee:

- (a) Provides written notice to the Director;
- (b) Describes the actions or procedures the Permittee will take to ensure that the well will not endanger USDWs during the period of inactivity. These actions and procedures shall include compliance with mechanical integrity demonstration, Financial Responsibility and all other permit requirements designed to protect USDWs; and

- (c) Receives written notice by the Director temporarily waiving plugging and abandonment requirements.

PART III. CONDITIONS APPLICABLE TO ALL PERMITS

Section A. EFFECT OF PERMIT

The Permittee is allowed to engage in underground injection in accordance with the conditions of this Permit. The Permittee shall not construct, operate, maintain, convert, plug, abandon, or conduct any other activity in a manner that allows the movement of fluid containing any contaminant into underground sources of drinking water, if the presence of that contaminant may cause a violation of any primary drinking water regulation under 40 CFR 142 or may otherwise adversely affect the health of persons. Any underground injection activity not authorized by this Permit or by rule is prohibited. Issuance of this Permit does not convey property rights of any sort or any exclusive privilege; nor does it authorize any injury to persons or property, any invasion of other private rights, or any infringement of State or local law or regulations. Compliance with the terms of this Permit does not constitute a defense to any enforcement action brought under the provisions of Section 1431 of the Safe Drinking Water Act (SDWA) or any other law governing protection of public health or the environment, for any imminent and substantial endangerment to human health or the environment, nor does it serve as a shield to the Permittee's independent obligation to comply with all UIC regulations. Nothing in this Permit relieves the Permittee of any duties under applicable regulations.

Section B. CHANGES TO PERMIT CONDITIONS

1. Modification, Reissuance, or Termination.

The Director may, for cause or upon a request from the Permittee, modify, revoke and reissue, or terminate this Permit in accordance with 40 CFR 124.5, 144.12, 144.39, and 144.40. Also, this Permit is subject to minor modification for causes as specified in 40 CFR 144.41. The filing of a request for modification, revocation and reissuance, termination, or the notification of planned changes or anticipated noncompliance on the part of the Permittee does not stay the applicability or enforceability of any condition of this Permit.

2. Conversions.

The Director may, for cause or upon a written request from the Permittee, allow conversion of the well from a Class II injection well to a non-Class II well. Conversion may not proceed until the Permittee receives written approval from the Director. Conditions of such conversion may include but are not limited to, approval of the proposed well rework, follow up demonstration of mechanical integrity, well-specific monitoring and reporting following the conversion, and demonstration of practical use of the converted configuration.

3. Transfer of Permit.

Under 40 CFR 144.38, this Permit is transferable provided the current Permittee notifies the Director at least thirty (30) days in advance of the proposed transfer date (EPA Form 7520-7) and provides a written agreement between the existing and new Permittees containing a specific date for transfer of Permit responsibility, coverage and liability between them. The notice shall adequately demonstrate that the financial responsibility requirements of 40 CFR 144.52(a)(7) will be met by the new Permittee. The Director may require modification or revocation and reissuance of the Permit to change the name of the Permittee and incorporate such other requirements as may be necessary under the Safe Drinking Water Act; in some cases, modification or revocation and reissuance is mandatory.

4. Permittee Change of Address.

Upon the Permittee's change of address, or whenever the operator changes the address where monitoring records are kept, the Permittee must provide written notice to the Director within 30 days.

5. Construction Changes, Workovers, Logging and Testing Data

The Permittee shall give advance notice to the Director, and shall obtain the Director's written approval prior to any physical alterations or additions to the permitted facility. Alterations or workovers shall meet all conditions as set forth in this permit. The Permittee shall record any changes to the well construction on a Well Rework Record (EPA Form 7520-12), and shall provide this and any other record of well workovers, logging, or test data to EPA within sixty (60) days of completion of the activity.

Following the completion of any well workovers or alterations which affect the casing, tubing, or packer, a successful demonstration of mechanical integrity (Part III, Section F of this permit) shall be made, and written authorization from the Director received, prior to resuming injection activities.

Section C. SEVERABILITY

The Provisions of this Permit are severable, and if any provision of this Permit or the application of any provision of this Permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this Permit shall not be affected thereby.

Section D. CONFIDENTIALITY

In accordance with 40 CFR Part 2 and 40 CFR 144.5, information submitted to EPA pursuant to this Permit may be claimed as confidential by the submitter. Any such claim must be asserted at the time of submission by stamping the words "confidential business information" on each page containing such information. If no claim is made at the time of submission, EPA may make the information available to the public without further notice. If a claim is asserted, the validity of the claim will be assessed in accordance with the procedures in 40 CFR Part 2 (Public Information). Claims of confidentiality for the following information will be denied:

- The name and address of the Permittee, and
- information which deals with the existence, absence or level of contaminants in drinking water.

Section E. GENERAL PERMIT REQUIREMENTS

1. Duty to Comply.

The Permittee must comply with all conditions of this Permit. Any noncompliance constitutes a violation of the Safe Drinking Water Act (SDWA) and is grounds for enforcement action; for Permit termination, revocation and reissuance, or modification; or for denial of a permit renewal application; except that the Permittee need not comply with the provisions of this Permit to the extent and for the duration such noncompliance is authorized in an emergency permit under 40 CFR 144.34. All violations of the SDWA may subject the Permittee to penalties and/or criminal prosecution as specified in Section 1423 of the SDWA.

2. Duty to Reapply.

If the Permittee wishes to continue an activity regulated by this Permit after the expiration date of this Permit, under 40 CFR 144.37 the Permittee must apply for a new permit prior to the expiration date.

3. Need to Halt or Reduce Activity Not a Defense.

It shall not be a defense for a Permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this Permit.

4. Duty to Mitigate.

The Permittee shall take all reasonable steps to minimize or correct any adverse impact on the environment resulting from noncompliance with this Permit.

5. Proper Operation and Maintenance.

The Permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the Permittee to achieve compliance with the conditions of this Permit. Proper operation and maintenance includes effective performance, adequate funding, adequate operator staffing and training, and adequate laboratory and process controls, including appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems only when necessary to achieve compliance with the conditions of this Permit.

6. Permit Actions.

This Permit may be modified, revoked and reissued or terminated for cause. The filing of a request by the Permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.

7. Property Rights.

This Permit does not convey any property rights of any sort, or any exclusive privilege.

8. Duty to Provide Information.

The Permittee shall furnish to the Director, within a time specified, any information which the Director may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit, or to determine compliance with this permit. The Permittee shall also furnish to the Director, upon request, copies of records required to be kept by this Permit. The Permittee is required to submit any information required by this Permit or by the Director to the mailing address designated in writing by the Director.

9. Inspection and Entry.

The Permittee shall allow the Director, or an authorized representative, upon the presentation of credentials and other documents as may be required by law, to:

- (a) Enter upon the Permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of this Permit;

- (b) Have access to and copy, at reasonable times, any records that must be kept under the conditions of this Permit;
- (c) Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this Permit; and,
- (d) Sample or monitor at reasonable times, for the purpose of assuring permit compliance or as otherwise authorized by the SDWA, any substances or parameters at any location.

10. Signatory Requirements.

All applications, reports or other information submitted to the Director shall be signed and certified according to 40 CFR 144.32. This section explains the requirements for persons duly authorized to sign documents, and provides wording for required certification.

11. Reporting Requirements.

- (a) **Planned changes.** The Permittee shall give notice to the Director as soon as possible of any planned changes, physical alterations or additions to the permitted facility, and prior to commencing such changes.
- (b) **Anticipated noncompliance.** The Permittee shall give advance notice to the Director of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.
- (c) **Monitoring Reports.** Monitoring results shall be reported at the intervals specified in this Permit.
- (d) **Compliance schedules.** Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this Permit shall be submitted no later than 30 days following each schedule date.
- (e) **Twenty-four hour reporting.** The Permittee shall report to the Director any noncompliance which may endanger human health or the environment, including:
 - (i) Any monitoring or other information which indicates that any contaminant may cause endangerment to a USDW; or
 - (ii) Any noncompliance with a permit condition or malfunction of the injection system which may cause fluid migration into or between USDWs.

Information shall be provided, either directly or by leaving a message, within twenty-four (24) hours from the time the permittee becomes aware of the circumstances by telephoning (800) 227-8917 and requesting EPA Region VIII UIC Program Compliance and Technical Enforcement Director, or by contacting the EPA Region VIII Emergency Operations Center at (303) 293-1788.

In addition, a follow up written report shall be provided to the Director within five (5) days of the time the Permittee becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause, the period of noncompliance including exact dates and times, and if the noncompliance has not been corrected the anticipated time it is expected to continue; and the steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance.

- (f) Oil Spill and Chemical Release Reporting: The Permittee shall comply with all reporting requirements related to the occurrence of oil spills and chemical releases by contacting the National Response Center (NRC) at (800) 424-8802, (202) 267-2675, or through the NRC website <http://www.nrc.uscg.mil/index.htm>.
- (g) Other Noncompliance. The Permittee shall report all instances of noncompliance not reported under paragraphs Part III, Section E Paragraph 11(b) or Section E, Paragraph 11(e) at the time the monitoring reports are submitted. The reports shall contain the information listed in Paragraph 11(e) of this Section.
- (h) Other information. Where the Permittee becomes aware that it failed to submit any relevant facts in the permit application, or submitted incorrect information in a permit application or in any report to the Director, the Permittee shall promptly submit such facts or information to the Director.

Section F. FINANCIAL RESPONSIBILITY

1. Method of Providing Financial Responsibility.

The Permittee shall maintain continuous compliance with the requirement to maintain financial responsibility and resources to close, plug, and abandon the underground injection well(s). No substitution of a demonstration of financial responsibility shall become effective until the Permittee receives written notification from the Director that the alternative demonstration of financial responsibility is acceptable. The Director may, on a periodic basis, require the holder of a permit to revise the estimate of the resources needed to plug and abandon the well to reflect changes in such costs and may require the Permittee to provide a revised demonstration of financial responsibility.

2. Insolvency.

In the event of:

- (a) the bankruptcy of the trustee or issuing institution of the financial mechanism; or
- (b) suspension or revocation of the authority of the trustee institution to act as trustee; or

- (c) the institution issuing the financial mechanism losing its authority to issue such an instrument

the Permittee must notify the Director in writing, within ten (10) business days, and the Permittee must establish other financial assurance or liability coverage acceptable to the Director within sixty (60) days after any event specified in (a), (b), or (c) above.

The Permittee must also notify the Director by certified mail of the commencement of voluntary or involuntary proceedings under Title 11 (Bankruptcy), U.S. Code naming the owner or operator as debtor, within ten (10) business days after the commencement of the proceeding. A guarantor, if named as debtor of a corporate guarantee, must make such a notification as required under the terms of the guarantee.

APPENDIX A

WELL CONSTRUCTION REQUIREMENTS

See diagram.

The Federal No. 15-12-9-17 was drilled to a total depth of 5767 feet (KB) in the Basal Carbonate Member of the Green River Formation.

Surface casing (8-5/8 inch) was set at a depth of 327 feet in a 12-1/4 inch hole using 150 sacks of Class "G" cement which was circulated to the surface.

Production casing (5-1/2 inch) was set at a depth of 5757.42 feet (KB) in a 7-7/8 inch hole with 285 sacks of Premium Lite II and 400 sacks of 50/50 poz mix. This well construction is considered adequate to protect USDW's.

The EPA calculates the top of cement as 1327 feet from the surface.

The schematic diagram shows the current injection perforations in the Garden Gulch, Douglas Creek Members of the Green River Formation. Additional perforations may be added at a later time between the depths of 3534 feet and the top of the Wasatch Formation (Estimated to be 5827 feet) provided the operator first notifies the Director and later submits an updated well completion report (EPA Form 7520-12) and schematic diagram.

The packer will be required to be set no higher than 100 feet above the top perforation.

Federal #15-12-9-17

Spud Date: 10/11/04
Put on Production: 12/28/04
GL: 5097' KB: 5109'

Proposed Injection Wellbore Diagram

Initial Production: BOPD,
MCFD. BWPD

SURFACE CASING

CSG SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 8 jts. (317.71')
DEPTH LANDED: 327.71' KB
HOLE SIZE: 12 1/4"
CEMENT DATA: 150 sks Class "G". Est 5 bbls cmt to surface.

PRODUCTION CASING

CSG SIZE: 5 1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 137 jts. (5755.42')
DEPTH LANDED: 5757.42' KB
HOLE SIZE: 7 7/8"
CEMENT DATA: 285 sks Prem. Lite II. 400 sks 50/50 poz.
CEMENT TOP AT: 260'

TUBING

SIZE/GRADE/WT.: 2 7/8" / J-55 / 6.5#
NO. OF JOINTS: 170 jts (5513.07')
TUBING ANCHOR: 5525.07' KB
NO. OF JOINTS: 1 jts (31.74')
SEATING NIPPLE: 2 7/8" (1.10')
SN LANDED AT: 5559.61' KB
NO. OF JOINTS: 2 jts (66.377')
TOTAL STRING LENGTH: EOT @ 5625.98'

FRAC JOB

12/21/04 5562'-5601' Frac CP4 & 5 sands as follows:
40,225#s of 20/40 sand in 422 bbls
Lightning 17 frac. Treated @ ave pressure of
942 w/ ave rate of 24.5 bpm. Calc flush 5559
gal. Actual flush: 5599 gal. ISIP 1280.

12/22/04 5395'-5413' Frac CP2 sands as follows:
29,582#s of 20/40 sand in 353 bbls Lightning
17 frac fluid. Treated @ ave pressure of 1250
w/ ave rate of 24.7 bpm w/ up to 8 ppg of
sand. Calc. flush 5393 gal. Actual flush 5393
gal. ISIP 1455.


12/22/04 4940'-4946' Frac A1 sands as follows:
14,813#s of 20/40 sand in 229 bbls Lightning
17 frac fluid. Treated @ ave pressure of 1962
w/ ave rate of 24.7 bpm. Calc. Flush 4938
gal. Actual Flush 4977 gal. ISIP 2000.

12/22/04 4735'-4786' Frac B1 & B.5 sands as follows:
48,957#s of 20/40 sand in 420 bbls Lightning
17 frac fluid. treated @ ave pressure of 2326
w/ ave rate of 24.6 bpm. Calc. Flush 4732 gal.
Actual Flush 4733. ISIP 2850.

12/22/04 4047'-4062' Frac GB6 sands as follows:
69,613#s of 20/40 sand in 532 bbls Lightning
17 frac fluid. Treated @ ave pressure of 1923
w/ ave rate of 24.6 bpm. Calc. flush 4045 gal.
Actual Flush 3961 gal. ISIP 2300.

PERFORATION RECORD

Date	Interval	Tool	Holes
12/16/04	5597'-5601'	4 JSPF	16 holes
12/16/04	5562'-5580'	4 JSPF	72 holes
12/21/04	5408'-5413'	4 JSPF	20 holes
12/21/04	5395'-5399'	4 JSPF	16 holes
12/22/04	4940'-4946'	4 JSPF	24 holes
12-22-04	4780'-4786'	4 JSPF	24 holes
12/22/04	4735'-4741'	4 JSPF	24 holes
12/22/04	4066'-4076'	4 JSPF	40 holes
12/22/04	4047'-4062'	4 JSPF	60 holes



NEWFIELD

Federal 15-12-9-17
659' FSL & 1981' FEL
SW/SE Section 12-T9S-R17E
Utah Co. Utah
API #43-047-35169; Lease #UTU-39713

APPENDIX B

LOGGING AND TESTING REQUIREMENTS

Logs.

Logs will be conducted according to current UIC guidance. It is the responsibility of the permittee to obtain and use guidance prior to conducting any well logging required as a condition of this permit.

NO LOGGING REQUIREMENTS

Tests.

Tests will be conducted according to current UIC guidance. It is the responsibility of the permittee to obtain and use guidance prior to conducting any well test required as a condition of this permit.

WELL NAME: Federal 15-12-9-17	
TYPE OF TEST	DATE DUE
Step Rate Test	Within 180 days following commencement of injection.
Standard Annulus Pressure	Prior to receiving authorization to inject and at least once every five (5) years thereafter.
Radioactive Tracer Survey (2)	Within 180 days following commencement of injection and at least once every five (5) years thereafter.
Pore Pressure	Prior to receiving authorization to inject.

APPENDIX C

OPERATING REQUIREMENTS

MAXIMUM ALLOWABLE INJECTION PRESSURE:

Maximum Allowable Injection Pressure (MAIP) as measured at the surface shall not exceed the pressure(s) listed below.

WELL NAME	MAXIMUM ALLOWED INJECTION PRESSURE (psi)
	ZONE 1 (Upper)
Federal 15-12-9-17	905

INJECTION INTERVAL(S):

Injection is permitted only within the approved injection interval listed below. Injection perforations may be altered provided they remain within the approved injection interval and the Permittee provides notice to the Director in accordance with Part II, Section A, Paragraph 6. Specific injection perforations can be found in Appendix A.

WELL NAME: Federal 15-12-9-17			
FORMATION NAME	APPROVED INJECTION INTERVAL (KB, ft)		FRACTURE GRADIENT (psi/ft)
	TOP	BOTTOM	
Green River	3,534.00 - 5,827.00		0.660

ANNULUS PRESSURE:

The annulus pressure shall be maintained at zero (0) psi as measured at the wellhead. If this pressure cannot be maintained, the Permittee shall follow the procedures listed under Part II, Section C. 6. of this permit.

MAXIMUM INJECTION VOLUME:

There is no limitation on the number of barrels per day (bbls/day) of water that shall be injected into this well, provided further that in no case shall injection pressure exceed that limit shown in Appendix C.

APPENDIX D

MONITORING AND REPORTING PARAMETERS

This is a listing of the parameters required to be observed, recorded, and reported. Refer to the permit Part II, Section D, for detailed requirements for observing, recording, and reporting these parameters.

OBSERVE MONTHLY AND RECORD AT LEAST ONCE EVERY THIRTY DAYS	
OBSERVE AND RECORD	Injection pressure (psig)
	Annulus pressure(s) (psig)
	Injection rate (bbl/day)
	Fluid volume injected since the well began injecting (bbls)

ANNUALLY	
ANALYZE	Injected fluid total dissolved solids (mg/l)
	Injected fluid specific gravity
	Injected fluid specific conductivity
	Injected fluid pH

ANNUALLY	
REPORT	Each month's maximum and averaged injection pressures (psig)
	Each month's maximum and averaged annulus pressure(s) (psig)
	Each month's averaged injection rate (bbl/day)
	Fluid volume injected since the well began injecting (bbl)
	Written results of annual injected fluid analysis
	Sources of all fluids injected during the year

Records of all monitoring activities must be retained and made available for inspection at the following location:

Newfield Production Company
1401 Seventeenth Street - Suite 1000
Denver, CO 80202

APPENDIX E

PLUGGING AND ABANDONMENT REQUIREMENTS

See diagram.

All cement plugs will be set with tubing.

9.2 ppg plugging gel, or fresh water weighted with bentonite or treated brine will be placed between all cement plugs.

The following Plugging and Abandonment Plan, as proposed by the permittee, is predicated on the permittee not revising the injection perforations cited on the schematic diagram of well construction/conversion. Should the uppermost perforations (4047 feet to 4062 feet) be modified in construction, the EPA will modify the P&A Plan accordingly.

PLUG NO. 1: A Cast Iron Bridge Plug (CIBP) at 3952 feet with 100 feet of Class "G" cement on CIBP.

PLUG NO. 2: A 225-foot Class "G" cement plug from 1975 feet to 2200 feet. This plug will cover both a water zone and the top of the Green River Formation.

PLUG NO. 3: A Class "G" cement plug from the surface to a depth of 397 feet within the 5-1/2 inch casing.

PLUG NO. 4: A Class "G" cement plug on the backside of the 5-1/2 inch casing from the surface to a depth of 397 feet.

Attachment Q-2

Federal #15-12-9-17

Spud Date: 10/11/04
Put on Production: 12/28/04
GL: 5097' KB: 5109'

Initial Production: BOPD,
MCFD, BWPD

Proposed P&A Wellbore Diagram

SURFACE CASING

CSG SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 8 jts. (317.71')
DEPTH LANDED: 327.71' KB
HOLE SIZE: 12 1/4"
CEMENT DATA: 150 sks Class "G", Est 5 bbls cmt to surface.

Base 4500's

Cement Top @ 260'

Pump 44 sx Class G Cement down 5 - 1/2" casing to 378'

Casing Shoe @ 328'

347'

PRODUCTION CASING

CSG SIZE: 5 1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 137 jts. (5755.42')
DEPTH LANDED: 5757.42' KB
HOLE SIZE: 7 7/8"
CEMENT DATA: 285 sks Prem. Lite II, 400 sks 30/30 per
CEMENT TOP AT: 260'

Green River 2025-

-1327' TOC/EPA

-1915' - 2000' - Cement Plug

Confine Zone 3480' - 3534'
Garden Gulch 3534'

-3690' - 4351' 80% Bond
100' (12 sx) Class G Cement plug on top of CIBP

CIBP @ 3952'

4047' - 4062'

4066' - 4076'

-4522' Douglas Creek

4735' - 4741'

4780' - 4786'

4940' - 4946'

5395' - 5399'

5408' - 5413'

5562' - 5580'

5597' - 5601'

-5701' base Carbonate
Top of Fill & PBTD @ 5711'

SHOE @ 5757.42'

TD @ 5767'

Est 5827' W28264

NEWFIELD

Federal 15-12-9-17
659' FSL & 1981' FEL
SW/SE Section 12-T9S-R17E
Uintah Co, Utah
API #43-047-35169; Lease #UTU-39713

APPENDIX F

CORRECTIVE ACTION REQUIREMENTS

No corrective action is deemed necessary for this project.

STATEMENT OF BASIS

NEWFIELD PRODUCTION COMPANY

**FEDERAL 15-12-9-17
UINTAH COUNTY, UT**

EPA PERMIT NO. UT21029-06982

CONTACT: Emmett Schmitz
U. S. Environmental Protection Agency
Ground Water Program, 8P-W-GW
999 18th Street, Suite 300
Denver, Colorado 80202-2466
Telephone: 1-800-227-8917 ext. 6174

RECEIVED

OCT 02 2006

DIV. OF OIL, GAS & MINING

This STATEMENT OF BASIS gives the derivation of site-specific UIC Permit conditions and reasons for them. Referenced sections and conditions correspond to sections and conditions in the Permit.

UIC Permits specify the conditions and requirements for construction, operation, monitoring and reporting, and plugging of injection wells to prevent the movement of fluids into underground sources of drinking water (USDWs). Under 40 CFR 144 Subpart D, certain conditions apply to all UIC Permits and may be incorporated either expressly or by reference. General Permit conditions for which content is mandatory and not subject to site-specific differences (40 CFR Parts 144, 146 and 147) are not discussed in this document.

Upon the Effective Date when issued, the Permit authorizes the conversion and operation of a "new" injection well or wells governed by the conditions specified in the Permit. The Permit is issued for the operating life of the injection well or project unless terminated for reasonable cause under 40 CFR 144.39, 144.40 and 144.41. The Permit is subject to EPA review at least once every five (5) years to determine if action is required under 40 CFR 144.36(a).

PART I. General Information and Description of Facility

Newfield Production Company
1401 Seventeenth Street
Suite 1000
Denver, CO 80202

on

September 26, 2005

submitted an application for an Underground Injection Control (UIC) Program Permit or Permit Modification for the following injection well or wells:

Federal 15-12-9-17
659' FSL & 1981' FEL, SWSE S12, T9S, R17E
Uintah County, UT

Regulations specific to Uintah-Ouray Indian Reservation injection wells are found at 40 CFR 147 Subpart TT.

The application, including the required information and data necessary to issue or modify a UIC Permit in accordance with 40 CFR Parts 144, 146 and 147, was reviewed and determined by EPA to be complete.

The Permit will expire upon delegation of primary enforcement responsibility (primacy) for applicable portions of the UIC Program to the Ute Indian Tribe or the State of Utah unless the delegated agency has the authority and chooses to adopt and enforce this Permit as a Tribal or State Permit.

TABLE 1.1 shows the status of the well or wells as "New", "Existing", or "Conversion" and for Existing shows the original date of injection operation. Well authorization "by rule" under 40 CFR Part 144 Subpart C expires automatically on the Effective Date of an issued UIC Permit.

The Federal No. 15-12-9-17 is currently an active Green River Formation oil well. The applicant intends to convert the subject well to an injection well to support existing Green River Formation enhanced oil recovery operations.

TABLE 1.1
WELL STATUS / DATE OF OPERATION

CONVERSION WELLS

Well Name	Well Status	Date of Operation
Federal 15-12-9-17	Conversion	N/A

PART II. Permit Considerations (40 CFR 146.24)

The proposed injection well is located in the Newfield Production Company Greater Monument Butte area near the center of the broad, gently northward dipping south flank of the Uinta Basin. The beds dip at about 200'/mile, and there are no known surface folds or faults in the field. The lower 600' to 800' of the Uinta Formation, generally consisting of 5' to 20' thick brown lenticular fluvial sandstone and interbedded varicolored shales, outcrops at the surface in this area. The Uinta is underlain by the Green River Formation which consists of lake (lacustrine) margin sandstones, limestone and shale beds that were deposited along the edges and on the broad level floor of Lake Uinta as it expanded and contracted through time. Underlying the Green River Formation is the Wasatch Formation, which is approximately 2400' thick in this area and consists of red alluvial shales and siltstone with scattered lenticular sandstones usually 10' to 50' thick. Below the Wasatch Formation is the Mesaverde Formation; a series of interbedded continental deposits of shale, sandstone, and coal. Water samples from Mesaverde sands in the nearby Natural Buttes Unit yield highly saline water.

The Uinta Basin is a topographic and structural trough encompassing an area of more than 9300 square mi (14,900 km) in northeast Utah. The basin is sharply asymmetrical, with a steep north flank bounded by the east-west-trending Uinta Mountains, and a gently dipping south flank. The Uinta Basin formed in Paleocene to Eocene time, creating a large area of internal drainage which was filled by ancestral Lake Uinta. Deposition in and around Lake Uinta consisted of open- to marginal-lacustrine sediments that make up the Green River Formation. Alluvial red-bed deposits that are laterally equivalent to and intertongue with the Green River make up the Colton Formation (Wasatch). More than 450 million barrels of oil (63 MT) have been produced from the Green River and Wasatch Formations in the Uinta Basin. The southern shore of Lake Uinta was very broad and flat, which allowed large transgressive and regressive shifts in the shoreline in response to climatic and tectonic-induced rise and fall of the lake. The cyclic nature of Green River deposition in the southern shore area resulted in numerous stacked deltaic deposits. Distributary-mouth bars, distributary channels, and near-shore bars are the primary producing sandstone reservoirs in the area (Ref: "Reservoir Characterization of the Lower Green River Formation, Southwest Uinta Basin, Utah Biannual Technical Progress Report 4/1/99 - 9/30/99", by C. D. Morgan, Program Manager, November 1999, Contract DE-AC26-98BC15103). The Tertiary Duchesne River Formation alluvium generally is present at the surface in this area.

Throughout the current Newfield Production Company area of enhanced recovery injection activity, i.e., T8-9S - R15-19E, Green River Formation water analyses generally exhibit total dissolved (TDS) content well in excess of 10,000 mg/l. A few recent applications for well conversion to enhanced recovery injection contain Green River water analyses with TDS approximating 10,000 mg/l. The State of Utah-Natural Resources ascribes low TDS values to several possibilities involving dilution of Green River water with high TDS values, e.g., recharge of the Green River Formation via Green River Formation outcrop on the Book Cliffs/Roan Cliffs; injection of very low TDS Johnson Water District Reservoir source water; and percolation of surface water via deep-seated Gilsonite veins penetrating lower Green River Members.

Geologic Setting (TABLE 2.1)

TABLE 2.1
GEOLOGIC SETTING
Federal 15-12-9-17

Formation Name	Top (ft)	Base (ft)	TDS (mg/l)	Lithology
Uinta	0.00	2,025.00	< 10,000.00	Predominantly fluvial sand and shale.
Green River	2,025.00	5,827.00	15,228.00	Predominately lacustrine carbonate, sand and shale with interbeds of fluvial sand and shale.

Proposed Injection Zone(s) (TABLE 2.2)

An injection zone is a geological formation, group of formations, or part of a formation that receives fluids through a well. The proposed injection zones are listed in TABLE 2.2.

Injection will occur into an injection zone that is separated from USDWs by a confining zone which is free of known open faults or fractures within the Area of Review.

The approved injection interval for enhanced recovery injection is the gross interval between the top of the Garden Gulch Member (3534 feet) and the top of the Wasatch Formation, estimated to be 5827 feet.

TABLE 2.2
INJECTION ZONES
Federal 15-12-9-17

Formation Name	Top (ft)	Base (ft)	TDS (mg/l)	Fracture Gradient (psi/ft)	Porosity	Exempted?*
Green River	3,534.00	5,827.00	15,228.00	0.660		N/A

* C - Currently Exempted
E - Previously Exempted
P - Proposed Exemption
N/A - Not Applicable

Confining Zone(s) (TABLE 2.3)

A confining zone is a geological formation, part of a formation, or a group of formations that limits fluid movement above the injection zone. The confining zone or zones are listed in TABLE 2.3.

The Green River Formation Confining Zone is located at the top of the Garden Gulch Member between the depths of 3480 feet and 3534 feet. No 80% bond index cement bond is present within the Confining Zone.

TABLE 2.3
CONFINING ZONES
Federal 15-12-9-17

Formation Name	Formation Lithology	Top (ft)	Base (ft)
Green River	Shale	3,480.00	3,534.00

Underground Sources of Drinking Water (USDWs) (TABLE 2.4)

Aquifers or the portions thereof which contain less than 10,000 mg/l total dissolved solids (TDS) and are being or could in the future be used as a source of drinking water are considered to be USDWs. The USDWs in the area of this facility are identified in TABLE 2.4.

The State of Utah "Water Wells and Springs", <http://NRWRT1.STATE.UT.US>, identifies no public water supply wells within the one-quarter (1/4) mile Area-of-Review (AOR) around the Federal No. 15-12-9-17.

Technical Publication No. 92: State of Utah, Department of Natural Resources, cites the base of Underground Sources of Drinking Water (USDW) in the Uinta Formation, approximately 347 feet from the surface.

TABLE 2.4
UNDERGROUND SOURCES OF DRINKING WATER (USDW)
Federal 15-12-9-17

Formation Name	Formation Lithology	Top (ft)	Base (ft)	TDS (mg/l)
Uinta	Predominantly fluvial sand and shale. Minor lacustrine deposition.	0.00	347.00	< 10,000.00

PART III. Well Construction (40 CFR 146.22)

The Federal No. 15-12-9-17 was drilled to a total depth of 5767 feet (KB) in the Basal Carbonate Member of the Green River Formation.

Surface casing (8-5/8 inch) was set at a depth of 327 feet in a 12-1/4 inch hole using 150 sacks of Class "G" cement which was circulated to the surface.

Production casing (5-1/2 inch) was set at a depth of 5757.42 feet (KB) in a 7-7/8 inch hole with 285 sacks of Premium Lite II and 400 sacks of 50/50 poz mix. This well construction is considered adequate to protect USDW's.

The EPA calculates the top of cement as 1327 feet from the surface.

The schematic diagram shows the current injection perforations in the Garden Gulch, Douglas Creek Members of the Green River Formation. Additional perforations may be added at a later time between the depths of 3534 feet and the top of the Wasatch Formation (Estimated to be 5827 feet) provided the operator first notifies the Director and later submits an updated well completion report (EPA Form 7520-12) and schematic diagram.

The packer will be required to be set no higher than 100 feet above the top perforation.

TABLE 3.1
WELL CONSTRUCTION REQUIREMENTS
Federal 15-12-9-17

Casing Type	Hole Size (in)	Casing Size (in)	Cased Interval (ft)	Cemented Interval (ft)
Production	7.88	5.50	0.00 - 5,757.42	1,327.00 - 5,767.00
Surface	12.25	8.63	0.00 - 327.71	0.00 - 327.71

The approved well completion plan will be incorporated into the Permit as APPENDIX A and will be binding on the Permittee. Modification of the approved plan is allowed under 40 CFR 144.52(a)(1) provided written approval is obtained from the Director prior to actual modification.

Casing and Cementing (TABLE 3.1)

The construction plan for the well or wells proposed for conversion to an injection well was evaluated and determined to be in conformance with standard practices and guidelines that ensure well injection does not result in the movement of fluids into USDWs. Well construction and conversion details for the well or wells are shown in TABLE 3.1.

Tubing and Packer

Injection tubing is required to be installed from a packer up to the surface inside the well casing. The packer will be set above the uppermost perforation. The tubing and packer are designed to prevent injection fluid from coming into contact with the outermost casing.

Tubing-Casing Annulus (TCA)

The TCA allows the casing, tubing and packer to be pressure-tested periodically for mechanical integrity, and will allow for detection of leaks. The TCA will be filled with fresh water treated with a corrosion inhibitor or other fluid approved by the Director.

The tubing/casing annulus must be kept closed at all times so that it can be monitored as required under the conditions of the Permit.

Monitoring Devices

The permittee will be required to install and maintain wellhead equipment that allows for monitoring pressures and providing access for sampling the injected fluid. Required equipment may include but is not limited to: 1) shut-off valves located at the wellhead on the injection tubing and on the TCA; 2) a flow meter that measures the cumulative volume of injected fluid; 3) fittings or pressure gauges attached to the injection tubing and the TCA for monitoring the injection and TCA pressure; and 4) a tap on the injection line, isolated by shut-off valves, for sampling the injected fluid.

All sampling and measurement taken for monitoring must be representative of the monitored activity.

PART IV. Area of Review, Corrective Action Plan (40 CFR 144.55)

**TABLE 4.1
AOR AND CORRECTIVE ACTION**

Well Name	Type	Status (Abandoned Y/N)	Total Depth (ft)	TOC Depth (ft)	CAP Required (Y/N)
Federal No. 10-12-9-17	Producer	No	5,832.00	295.00	No
Federal No. 14-12-9-17	Producer	No	5,740.00	1,300.00	No
Federal No. 16-12-9-17	Producer	No	5,770.00	1,330.00	No

TABLE 4.1 lists the wells in the Area of Review ("AOR") and shows the well type, operating status, depth, top of casing cement ("TOC") and whether a Corrective Action Plan ("CAP") is required for the well.

Area Of Review

Applicants for Class I, II (other than "existing" wells) or III injection well Permits are required to identify the location of all known wells within the injection well's Area of Review (AOR) which penetrate the injection zone, or in the case of Class II wells operating over the fracture pressure of the formation, all known wells within the area of review that penetrate formations which may be affected by increased pressure. Under 40 CFR 146.6 the AOR may be a fixed radius of not less than one quarter (1/4) mile or a calculated zone of endangering influence. For Area Permits, a fixed width of not less than one quarter (1/4) mile for the circumscribing area may be used.

Corrective Action Plan

For wells in the AOR which are improperly sealed, completed, or abandoned, the applicant shall develop a Corrective Action Plan (CAP) consisting of the steps or modifications that are necessary

to prevent movement of fluid into USDWs.

The CAP will be incorporated into the Permit as APPENDIX F and become binding on the permittee.

TABLE 4.1 lists the wells in the AOR, and shows the well type, operating status, depth, top of casing cement and whether a CAP is required for this well.

PART V. Well Operation Requirements (40 CFR 146.23)

TABLE 5.1
INJECTION ZONE PRESSURES
Federal 15-12-9-17

Formation Name	Depth Used to Calculate MAIP (ft)	Fracture Gradient (psi/ft)	Initial MAIP (psi)
Green River	4,047.00	0.660	905

Approved Injection Fluid

The approved injection fluid is limited to Class II injection well fluids pursuant to 40 CFR § 144.6(b). For disposal wells injecting water brought to the surface in connection with natural gas storage operations, or conventional oil or natural gas production, the fluid may be commingled and the well used to inject other Class II wastes such as drilling fluids and spent well completion, treatment and stimulation fluid. Injection of non-exempt wastes, including unused fracturing fluids or acids, gas plant cooling tower cleaning wastes, service wastes and vacuum truck wastes, is prohibited.

The proposed injectate is a blend of source water from the Johnson Water District reservoir and produced water from adjacent wells. The TDS of the injectate is 9967 mg/l.

Injection Pressure Limitation

Injection pressure, measured at the wellhead, shall not exceed a maximum calculated to assure that the pressure used during injection does not initiate new fractures or propagate existing fractures in the confining zones adjacent to the USDWs.

The applicant submitted injection fluid density and injection zone data which was used to calculate a formation fracture pressure and to determine the maximum allowable injection pressure (MAIP), as measured at the surface, for this Permit,

TABLE 5.1 lists the fracture gradient for the injection zone and the approved MAIP, determined according to the following formula:

$$FP = [fg - (0.433 * sg)] * d$$

FP = formation fracture pressure (measured at surface)

fg = fracture gradient (from submitted data or tests)

sg = specific gravity (of injected fluid)

d = depth to top of injection zone (or top perforation)

Injection Volume Limitation

Cumulative injected fluid volume limits are set to assure that injected fluids remain within the boundary of the exempted area. Cumulative injected fluid volume is limited when injection occurs into an aquifer that has been exempted from protection as a USDW.

There will be no restrictions on the cumulative volume of authorized fluid injected into the approved injection interval.

Mechanical Integrity (40 CFR 146.8)

An injection well has mechanical integrity if:

1. there is no significant leak in the casing, tubing, or packer (Part I); and
2. there is no significant fluid movement into a USDW through vertical channels adjacent to the injection well bore (Part II).

The Permit prohibits injection into a well which lacks mechanical integrity.

The Permit requires that the well demonstrate mechanical integrity prior to injection and periodically thereafter. A demonstration of mechanical integrity includes both internal (Part I) and external (Part II). The methods and frequency for demonstrating Part I and Part II mechanical integrity are dependent upon well-specific conditions as explained below.

Well construction and site-specific conditions dictate the following requirements for Mechanical Integrity (MI) demonstrations:

PART I MI: Internal MI will be demonstrated prior to beginning injection. Since this well is constructed with a standard casing, tubing, and packer configuration, a successful mechanical integrity test (MIT) is required to take place at least once every five (5) years. A demonstration of Part I MI is also required prior to resuming injection following any workover operation that affects the casing, tubing or packer. Part I MI may be demonstrated by a standard tubing-casing annulus pressure test using the maximum permitted injection pressure or 1000 psi, whichever is less, with a ten (10) percent or less pressure loss over thirty (30) minutes.

PART II MI: - The CBL indicates that cement does not meet minimum requirements needed to demonstrate zone isolation (at least 18 feet of continuous 80% bond, or better) through the confining zone. Therefore, further testing for Part II MI will be required prior to injection and at least once every five years thereafter. The demonstration shall be by temperature survey or other approved test. Approved tests for demonstrating Part II MI include a temperature survey, noise log or oxygen activation log, and Region 8 may also accept results of a radioactive tracer survey under certain circumstances.

PART VI. Monitoring, Recordkeeping and Reporting Requirements

Injection Well Monitoring Program

At least once a year the permittee must analyze a sample of the injected fluid for total dissolved solids (TDS), specific conductivity, pH, and specific gravity. This analysis shall be reported to EPA annually as part of the Annual Report to the Director. Any time a new source of injected fluid is added, a fluid analysis shall be made of the new source.

Instantaneous injection pressure, injection flow rate, cumulative fluid volume and TCA pressures must be observed on a weekly basis. A recording, at least once every thirty (30) days, must be made of the injection pressure, injection flow rate and cumulative fluid volume, and the maximum and average value for each must be determined for each month. This information is required to be reported annually as part of the Annual Report to the Director.

PART VII. Plugging and Abandonment Requirements (40 CFR 146.10)

Plugging and Abandonment Plan

Prior to abandonment, the well or wells must be plugged with cement in a manner which will not allow the movement of fluids either into or between USDWs. The plugging and abandonment plan is described in Appendix E of the Permit.

All cement plugs will be set with tubing.

9.2 ppg plugging gel, or fresh water weighted with bentonite or treated brine will be placed between all cement plugs.

The following Plugging and Abandonment Plan, as proposed by the permittee, is predicated on the permittee not revising the injection perforations cited on the schematic diagram of well construction/conversion. Should the uppermost perforations (4047 feet to 4062 feet) be modified in construction, the EPA will modify the P&A Plan accordingly.

PLUG NO. 1: A Cast Iron Bridge Plug (CIBP) at 3952 feet with 100 feet of Class "G" cement on CIBP.

PLUG NO. 2: A 225-foot Class "G" cement plug from 1975 feet to 2200 feet. This plug will cover both a water zone and the top of the Green River Formation.

PLUG NO. 3: A Class "G" cement plug from the surface to a depth of 397 feet within the 5-1/2 inch casing.

PLUG NO. 4: A Class "G" cement plug on the backside of the 5-1/2 inch casing from the surface to a depth of 397 feet.

PART VIII. Financial Responsibility (40 CFR 144.52)

Demonstration of Financial Responsibility

The permittee is required to maintain financial responsibility and resources to close, plug, and abandon the underground injection operation in a manner prescribed by the Director. The permittee shall show evidence of such financial responsibility to the Director by the submission of a surety bond, or other adequate assurance such as financial statements or other materials acceptable to the Director. The Regional Administrator may, on a periodic basis, require the holder of a lifetime permit to submit a revised estimate of the resources needed to plug and abandon the well to reflect inflation of such costs, and a revised demonstration of financial responsibility if necessary. Initially, the operator has chosen to demonstrate financial responsibility with:

Financial Statement reviewed and approved by the EPA on August 2, 2006. The EPA has

approved the estimate of \$33,500 to plug and abandon the Federal No. 15-12-9-17.

Financial Statement, received April 22, 2005

Evidence of continuing financial responsibility is required to be submitted to the Director annually.



United States Environmental Protection Agency
Washington, DC 20460

Application To Transfer Permit

Name and Address of Existing Permittee

Name and Address of Surface Owner

Locate Well and Outline Unit on
Section Plat- 640 Acres.

N									
S									
W					E				

State

County

Permit Number

Surface Location Description

1/4 of 1/4 of 1/4 of 1/4 of Section Township Range

Locate well in two directions from nearest lines of quarter section and drilling unit

Surface

Location ft. from (N/S) Line of quarter section
and ft. from (E/W) Line of quarter section.

Well Activity

Well Status

Type of Permit

Class I

Operating

Individual

Class II

Modification/Conversion

Area

Brine Disposal

Proposed

Number of Wells

Enhanced Recovery

Hydrocarbon Storage

Class III

Other

Lease Number

Well Number

Name(s) and Address(es) of New Owners(s)

Name and Address of New Operator

Attach to this application a written agreement between the existing and new permittee containing a specific date for transfer of permit responsibility, coverage, and liability between them.

The new permittee must show evidence of financial responsibility by the submission of a surety bond, or other adequate assurance, such as financial statements or other materials acceptable to the Director.

Certification

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

Name and Official Title (Please type or print)


Signature

Date Signed



United States Environmental Protection Agency
Washington, DC 20460

**COMPLETION REPORT FOR BRINE DISPOSAL,
HYDROCARBON STORAGE, OR ENHANCED RECOVERY**

Name and Address of Existing Permittee			Name and Address of Surface Owner		
<p>Locate Well and Outline Unit on Section Plat - 640 Acres</p> <div style="text-align: center;"> N  S W E </div>			State	County	Permit Number
			Surface Location Description ____ 1/4 of ____ 1/4 of ____ 1/4 of ____ 1/4 of Section ____ Township ____ Range ____		
			Locate well in two directions from nearest lines of quarter section and drilling unit Surface Location ____ ft. frm (N/S) ____ Line of quarter section and ____ ft. from (E/W) ____ Line of quarter section.		
			WELL ACTIVITY <input type="checkbox"/> Brine Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage	TYPE OF PERMIT <input type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells ____	Estimated Fracture Pressure of Injection Zone
			Anticipated Daily Injection Volume (Bbls) Average _____ Maximum _____		Injection Interval Feet _____ to Feet _____
Anticipated Daily Injection Pressure (PSI) Average _____ Maximum _____		Depth to Bottom of Lowermost Freshwater Formation (Feet)			
Type of Injection Fluid (Check the appropriate block(s)) <input type="checkbox"/> Salt Water <input type="checkbox"/> Brackish Water <input type="checkbox"/> Fresh Water <input type="checkbox"/> Liquid Hydrocarbon <input type="checkbox"/> Other			Lease Name	Well Number	
Date Drilling Began			Date Well Completed		
Date Drilling Completed			Name of Injection Zone		
Date Drilling Completed			Permeability of Injection Zone		
Date Drilling Completed			Porosity of Injection Zone		
CASING AND TUBING			CEMENT		
OD Size	Wt/Ft - Grade - New or Used	Depth	Sacks	Class	HOLE
Depth	Sacks	Class	Depth	Bit Diameter	Bit Diameter
INJECTION ZONE STIMULATION			WIRE LINE LOGS, LIST EACH TYPE		
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals
Interval Treated	Materials and Amount Used		Log Types		Logged Intervals

ATTACHMENTS

- A. Present a schematic or other appropriate drawing of the surface and subsurface construction details of the well as built.
- B. Describe the method and results of mechanical integrity testing.
- C. Present the results of that portion of those logs, test, and cores which specifically relate to (1) underground sources of drinking water and the confining zone(s) and (2) the injection and adjacent formations.
- D. Present the status of corrective action on defective wells in the area of review.
- E. Provide to EPA, with the completion report, one final print of all geophysical logs run.

PAPERWORK REDUCTION ACT

The public reporting and record keeping burden for this collection of information is estimated to average 4 hours per well. Burden means the total time, effort, or financial resource expended by persons to generate, maintain, retain, or disclose or provide information to or for a Federal Agency. This includes the time needed to review instructions; develop, acquire, install, and utilize technology and systems for the purposes of collecting, validating, and verifying information, processing and maintaining information, and disclosing and providing information; adjust the existing ways to comply with any previously applicable instructions and requirements; train personnel to be able to respond to the collection of information; search data sources; complete and review the collection of information; and, transmit or otherwise disclose the information. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates, and any suggested methods for minimizing respondent burden, including the use of automated collection techniques to Director, Collection Strategies Division, U.S. Environmental Protection Agency (2822), 1200 Pennsylvania Ave., NW., Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed forms to this address.

ANNUAL DISPOSAL/INJECTION WELL MONITORING REPORT

Name and Address of Surface Owner

Permit Number

Surface Location Description

1/4 of _____ 1/4 of _____ 1/4 of _____ 1/4 of _____ Section _____ Township _____ Range _____

Locate well in two directions from nearest lines of quarter section and drilling unit

Surface

Location _____ ft. frm (N/S) _____ Line of quarter section

and _____ ft. from (E/W) _____ Line of quarter section.

WELL ACTIVITY

TYPE OF PERMIT

☐ **Brine Disposal**☐ individual☐ Enhanced Recovery

Area

Hydrocarbon Storage

Number of Wells _____

Lease Name

Well Number

INJECTION PRESSURE

TOTAL VOLUME INJECTED

**TUBING -- CASING ANNULUS PRESSURE
(OPTIONAL MONITORING)**

MONTH

YEAR

AVERAGE PSIG

MAXIMUM PSIG

BBL

MCF

MINIMUM PSIG

MAXIMUM PSIG

Certification

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

Name and Official Title (Please type or print)

Signature _____

Date Signed _____

PAPERWORK REDUCTION ACT

The public reporting and record keeping burden for this collection of information is estimated to average 25 hours annually for operators of Class I wells and 5 hours annually for operators of Class II wells. Burden means the total time, effort, or financial resource expended by persons to generate, maintain, retain, or disclose or provide information to or for a Federal Agency. This includes the time needed to review instructions; develop, acquire, install, and utilize technology and systems for the purposes of collecting, validating, and verifying information, processing and maintaining information, and disclosing and providing information; adjust the existing ways to comply with any previously applicable instructions and requirements; train personnel to be able to respond to the collection of information; search data sources; complete and review the collection of information; and, transmit or otherwise disclose the information. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates, and any suggested methods for minimizing respondent burden, including the use of automated collection techniques to Director, Collection Strategies Division, U.S. Environmental Protection Agency (2822), 1200 Pennsylvania Ave., NW, Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed forms to this address.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:

U-39713

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

SUNDANCE UNIT

8. WELL NAME and NUMBER:

FEDERAL 15-12-9-17

9. API NUMBER:

4304735169

10. FIELD AND POOL, OR WILDCAT:

MONUMENT BUTTE

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL:

OIL WELL ☒

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

NEWFIELD PRODUCTION COMPANY

3. ADDRESS OF OPERATOR:

Route 3 Box 3630

CITY Myton

STATE UT

ZIP 84052

PHONE NUMBER

435.646.3721

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 659 FSL 1981 FEL

COUNTY: UINTAH

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SWSE, 12, T9S, R17E

STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: <u>10/16/2006</u>	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input checked="" type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: -	
	<input checked="" type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The subject well has been converted from a producing oil well to an injection well on 10/16/06. On 10/25/06 Dan Jackson with the EPA was contacted concerning the initial MIT on the above listed well. Permission was given at that time to perform the test on 10/27/06. On 10/27/06 the casing was pressured up to 1220 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 100 psig during the test. There was not an EPA representative available to witness the test. EPA# UT21029-06982 API# 43-047-35169

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) Callie Ross

TITLE Production Clerk

SIGNATURE

Callie Ross

DATE 11/08/2006

(This space for State use only)

**RECEIVED
NOV 13 2006**

DIV. OF OIL, GAS & MINING

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 1 / 1 / _____

Test conducted by: Trefley J. Rizer

Others present: _____

Well Name: <u>Federal 15-12-9-17</u>	Type: ER SWD	Status: AC TA UC
Field: <u>MONUMENT BUTTE</u>		
Location: <u>SU/SE</u> Sec: <u>12</u> T <u>9</u> N <u>10</u> R <u>17</u> E W County: <u>UNITA</u> State: <u>UT</u>		
Operator: <u>Newfield</u>		
Last MIT: <u>1</u> / <u>1</u> / _____	Maximum Allowable Pressure: _____ PSIG	

Is this a regularly scheduled test? ☐ Yes ☒ No
 Initial test for permit? ☒ Yes ☐ No
 Test after well rework? ☐ Yes ☒ No
 Well injecting during test? ☐ Yes ☒ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 0 psig


MIT DATA TABLE		Test #1	Test #2	Test #3
TUBING PRESSURE				
Initial Pressure	<u>100</u> psig	psig	psig	psig
End of test pressure	<u>100</u> psig	psig	psig	psig
CASING / TUBING ANNULUS PRESSURE				
0 minutes	<u>1220</u> psig	psig	psig	psig
5 minutes	<u>1220</u> psig	psig	psig	psig
10 minutes	<u>1220</u> psig	psig	psig	psig
15 minutes	<u>1220</u> psig	psig	psig	psig
20 minutes	<u>1220</u> psig	psig	psig	psig
25 minutes	<u>1220</u> psig	psig	psig	psig
30 minutes	<u>1220</u> psig	psig	psig	psig
_____ minutes	psig	psig	psig	psig
_____ minutes	psig	psig	psig	psig
RESULT	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test ? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____



UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

NEWFIELD PRODUCTION COMPANY

3a. Address

Route 3 Box 3630

Myton, UT 84052

3b. Phone (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

659 FSL 1981 FEL

SWSE Section 12 T9S R17E

5. Lease Serial No.

USA UTU-39713

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or

SUNDANCE UNIT

8. Well Name and No.

FEDERAL 15-12-9-17

9. API Well No.

4304735169

10. Field and Pool, or Exploratory Area

MONUMENT BUTTE

11. County or Parish, State

UINTAH, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Change Status, Put Well
	<input checked="" type="checkbox"/> Convert to	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	on Injection

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The above referenced well was put on injection at 9:30 a.m. on 12/13/06.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

I hereby certify that the foregoing is true and correct (Printed/ Typed)

Mandie Crozier

Signature

Title

Regulatory Specialist

Date

12/15/2006

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

RECEIVED

DEC 18 2006

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE. Other instructions on reverse side.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

NEWFIELD PRODUCTION COMPANY

3a. Address

Route 3 Box 3630
Myton, UT 84052

3b. Phone (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

659 FSL 1981 FEL

SWSE Section 12 T9S R17E

5. Lease Serial No.

USA UTU-39713

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or

SUNDANCE UNIT

8. Well Name and No.

FEDERAL 15-12-9-17

9. API Well No.

4304735169

10. Field and Pool, or Exploratory Area

MONUMENT BUTTE

11. County or Parish, State

UINTAH, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Step Rate Test _____
	<input type="checkbox"/> Convert to	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomple in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

A step rate test was conducted on the subject well on January 25, 2007. Results from the test indicate that the fracture gradient is .663 psi/ft. Therefore, Newfield is requesting that the maximum allowable injection pressure (MAIP) be changed to 905 psi.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

I hereby certify that the foregoing is true and
correct (Printed/ Typed)

Chevenne Bateman

Signature

Title

Well Analyst Foreman

Date

01/31/2007

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or
certify that the applicant holds legal or equitable title to those rights in the subject lease
which would entitle the applicant to conduct operations thereon.

Title

Date

Office


Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

FEB 05 2007


OF OIL, GAS & MINING

Federal 15-12-9-17
Sundance Unit
Step Rate Test
January 25, 2007



Start Pressure: 415 psi
Instantaneous Shut-In Pressure (ISIP): 955 psi
Top Perforation: 4047 feet
Fracture pressure (Pfp): 905 psi
FG: 0.663 psi/ft

Step	Rate(bpd)	Pressure(psi)
1	100	490
2	200	580
3	300	665
4	400	755
5	500	845
6	600	915
7	700	960
8	800	995



GRAPHIC CONTROLS CORPORATION
BUFFALO, NEW YORK

CHART NO. MC M-2500-H

METER _____

1-25-07

CHART PUT ON

5:30 AM

1-25-07

TAKEN OFF

3:00 PM

LOCATION

Federal 15-12-9-17

REMARKS

SRT

gubbert

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:

USA UTU-39713

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

GMBU

1. TYPE OF WELL:

OIL WELL ☒

GAS WELL ☐

OTHER

8. WELL NAME and NUMBER:

FEDERAL 15-12-9-17

2. NAME OF OPERATOR:

NEWFIELD PRODUCTION COMPANY

9. API NUMBER:

4304735169

3. ADDRESS OF OPERATOR:

Route 3 Box 3630

CITY Myton

STATE UT

ZIP 84052

PHONE NUMBER

435.646.3721

10. FIELD AND POOL, OR WILDCAT:

GREATER MB UNIT

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 659 FSL 1981 FEL

COUNTY: UINTAH

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SWSE, 12, T9S, R17E

STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 10/12/2010	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Step Rate Test
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

A step rate test was conducted on the subject well on October 12, 2010. Results from the test indicate that the fracture gradient is 0.820 psi/ft. Therefore, Newfield is requesting that the maximum allowable injection pressure (MAIP) be changed from 1535 psi to 905 psi.

EPA: UT21029-06982 API: 43-047-35169

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) Lucy Chavez-Naupoto

TITLE Administrative Assistant

SIGNATURE

DATE 11/10/2010

(This space for State use only)

RECEIVED

NOV 16 2010

DIV. OF OIL, GAS & MINING

Step Rate Test (SRT) Analysis

Date: 10/19/2010

Operator:

Newfield Production Company

Well:

Federal 15-12-9-17

Permit #:

UT21029-06982

Enter the following data :

Specific Gravity (sg) of injectate =	<u>1.015</u>	g/cc	
Depth to top perforation (D) =	<u>4047</u>	feet	4047
Top of permitted injection zone depth (blank=use top perforation to calculate fg) =		feet	
Estimated Formation Parting Pressure (P _{fp}) from SRT chart =	<u>1540</u>	psi	
Instantaneous Shut In Pressure (ISIP) from SRT =	<u>1634</u>	psi	1540
Bottom Hole Parting Pressure (P _{bhp}) from downhole pressure recorder =		psi	no downhole

Part One - Calculation of Fracture Gradient (fg)

Calculated Fracture Gradient = 0.820 psi/ft.

where: $fg = P_{bhp} / D$ (Note: this formula uses the downhole recorded bottom hole parting pressure if available) = 1634

D = depth used = 4047

P_{bhp} used = 3319

Calculated Bottom Hole Parting Pressure (P_{bhp}) = 3319 psi

3318.636

to calculate Bottom Hole Parting Pressure (P_{bhp}) = Formation Fracture Pressure (ISIP or P_{fp}) + (0.433 * SG * D)

(Use lesser of ISIP or P_{fp}) Value used = 1540

Part Two - Calculation of Maximum Allowable Injection Pressure (MAIP)


Maximum Allowable Injection Pressure (MAIP) = 1535 psi

D = depth used = 4047

MAIP = $[fg - (0.433 * SG)] * D = 1539.904$

(rounded down to nearest 5 psi)

Federal 15-12-9-17
Greater Monument Butte Unit
Step Rate Test
October 12, 2010



Start Pressure: 792 psi
Instantaneous Shut In Pressure (ISIP): 1634 psi
Top Perforation: 4047 feet
Fracture pressure (Pfp): 1540 psi
FG: 0.820 psi/ft

Step	Rate(bpd)	Pressure(psi)
1	100	845
2	200	1019
3	300	1208
4	400	1408
5	500	1548
6	600	1644
7	700	1690


PSIA

Absolute Pressure

Federal 15-12-9-17 SRT (10-12-10)

Device - PrTemp1000
Serial Number - M75866
Device ID - PrTemp


PSIA



Report Name: PrTemp1000 Data Table
 Report Date: Oct 12, 2010 02:20:49 PM MDT
 File Name: C:\Program Files\PTC® Instruments 2.00\Federal 15-12-9-17 SRT (10-12-10).csv
 Title: Federal 15-12-9-17 SRT (10-12-10)
 Device: PrTemp1000 - Temperature and Pressure Recorder
 Hardware Revision: REV2C (64K)
 Serial Number: M75866
 Device ID: PrTemp
 Data Start Date: Oct 12, 2010 04:00:00 AM MDT
 Data End Date: Oct 12, 2010 11:29:59 AM MDT
 Reading Rate: 2 Seconds
 Readings: 1 to 91 of 91
 Last Calibration Date: May 22, 2009
 Next Calibration Date: May 22, 2010

<u>Reading</u>	<u>Date and Time (MDT)</u>	<u>Absolute Pressure</u>	<u>Annotation</u>
1	Oct 12, 2010 04:00:00 AM	792.800	PSIA
2	Oct 12, 2010 04:04:59 AM	792.200	PSIA
3	Oct 12, 2010 04:09:59 AM	792.400	PSIA
4	Oct 12, 2010 04:14:59 AM	792.200	PSIA
5	Oct 12, 2010 04:20:00 AM	792.800	PSIA
6	Oct 12, 2010 04:24:59 AM	791.800	PSIA
7	Oct 12, 2010 04:30:01 AM	792.400	PSIA
8	Oct 12, 2010 04:35:00 AM	803.800	PSIA
9	Oct 12, 2010 04:40:00 AM	816.200	PSIA
10	Oct 12, 2010 04:45:00 AM	816.800	PSIA
11	Oct 12, 2010 04:49:59 AM	825.000	PSIA
12	Oct 12, 2010 04:54:59 AM	830.000	PSIA
13	Oct 12, 2010 04:59:59 AM	834.000	PSIA
14	Oct 12, 2010 05:05:01 AM	836.600	PSIA
15	Oct 12, 2010 05:09:59 AM	838.200	PSIA
16	Oct 12, 2010 05:15:00 AM	839.200	PSIA
17	Oct 12, 2010 05:19:59 AM	840.000	PSIA
18	Oct 12, 2010 05:25:00 AM	842.400	PSIA
19	Oct 12, 2010 05:30:06 AM	844.600	PSIA
20	Oct 12, 2010 05:35:00 AM	889.800	PSIA
21	Oct 12, 2010 05:39:59 AM	915.800	PSIA
22	Oct 12, 2010 05:44:59 AM	933.800	PSIA
23	Oct 12, 2010 05:50:00 AM	948.800	PSIA
24	Oct 12, 2010 05:54:59 AM	960.800	PSIA
25	Oct 12, 2010 06:00:09 AM	969.800	PSIA
26	Oct 12, 2010 06:04:59 AM	980.800	PSIA
27	Oct 12, 2010 06:10:00 AM	990.000	PSIA
28	Oct 12, 2010 06:14:59 AM	997.000	PSIA
29	Oct 12, 2010 06:19:59 AM	1003.400	PSIA
30	Oct 12, 2010 06:25:00 AM	1011.800	PSIA
31	Oct 12, 2010 06:29:59 AM	1018.600	PSIA
32	Oct 12, 2010 06:35:00 AM	1053.200	PSIA
33	Oct 12, 2010 06:40:06 AM	1074.400	PSIA
34	Oct 12, 2010 06:45:00 AM	1102.400	PSIA
35	Oct 12, 2010 06:49:59 AM	1122.200	PSIA
36	Oct 12, 2010 06:55:01 AM	1138.800	PSIA
37	Oct 12, 2010 07:00:00 AM	1155.400	PSIA
38	Oct 12, 2010 07:04:59 AM	1166.800	PSIA
39	Oct 12, 2010 07:10:00 AM	1175.400	PSIA
40	Oct 12, 2010 07:14:59 AM	1186.200	PSIA
41	Oct 12, 2010 07:20:01 AM	1195.400	PSIA
42	Oct 12, 2010 07:24:59 AM	1203.600	PSIA
43	Oct 12, 2010 07:30:00 AM	1208.200	PSIA
44	Oct 12, 2010 07:34:59 AM	1251.800	PSIA
45	Oct 12, 2010 07:40:00 AM	1278.600	PSIA
46	Oct 12, 2010 07:44:59 AM	1300.800	PSIA
47	Oct 12, 2010 07:49:59 AM	1317.200	PSIA
48	Oct 12, 2010 07:54:59 AM	1328.000	PSIA
49	Oct 12, 2010 07:59:59 AM	1342.600	PSIA
50	Oct 12, 2010 08:05:00 AM	1359.000	PSIA
51	Oct 12, 2010 08:09:59 AM	1370.600	PSIA
52	Oct 12, 2010 08:15:00 AM	1382.800	PSIA
53	Oct 12, 2010 08:20:00 AM	1391.800	PSIA
54	Oct 12, 2010 08:25:00 AM	1401.400	PSIA
55	Oct 12, 2010 08:29:59 AM	1408.400	PSIA
56	Oct 12, 2010 08:34:59 AM	1448.200	PSIA
57	Oct 12, 2010 08:39:59 AM	1467.800	PSIA
58	Oct 12, 2010 08:44:59 AM	1480.800	PSIA
59	Oct 12, 2010 08:50:00 AM	1496.800	PSIA
60	Oct 12, 2010 08:55:00 AM	1507.600	PSIA

61	Oct 12, 2010 09:00:00 AM	1517.000	PSIA
62	Oct 12, 2010 09:04:59 AM	1526.400	PSIA
63	Oct 12, 2010 09:10:00 AM	1516.600	PSIA
64	Oct 12, 2010 09:15:00 AM	1524.200	PSIA
65	Oct 12, 2010 09:20:00 AM	1535.000	PSIA
66	Oct 12, 2010 09:24:59 AM	1541.200	PSIA
67	Oct 12, 2010 09:30:00 AM	1548.400	PSIA
68	Oct 12, 2010 09:35:00 AM	1576.600	PSIA
69	Oct 12, 2010 09:39:59 AM	1589.000	PSIA
70	Oct 12, 2010 09:45:00 AM	1597.600	PSIA
71	Oct 12, 2010 09:49:59 AM	1608.600	PSIA
72	Oct 12, 2010 09:55:00 AM	1615.400	PSIA
73	Oct 12, 2010 09:59:59 AM	1616.400	PSIA
74	Oct 12, 2010 10:04:59 AM	1622.200	PSIA
75	Oct 12, 2010 10:09:59 AM	1628.200	PSIA
76	Oct 12, 2010 10:14:59 AM	1630.600	PSIA
77	Oct 12, 2010 10:20:00 AM	1633.600	PSIA
78	Oct 12, 2010 10:24:59 AM	1642.200	PSIA
79	Oct 12, 2010 10:30:00 AM	1643.800	PSIA
80	Oct 12, 2010 10:34:59 AM	1665.000	PSIA
81	Oct 12, 2010 10:40:00 AM	1670.600	PSIA
82	Oct 12, 2010 10:45:00 AM	1677.400	PSIA
83	Oct 12, 2010 10:50:00 AM	1686.400	PSIA
84	Oct 12, 2010 10:54:59 AM	1686.000	PSIA
85	Oct 12, 2010 10:59:59 AM	1691.800	PSIA
86	Oct 12, 2010 11:05:00 AM	1692.400	PSIA
87	Oct 12, 2010 11:09:59 AM	1696.800	PSIA
88	Oct 12, 2010 11:15:00 AM	1694.400	PSIA
89	Oct 12, 2010 11:20:00 AM	1690.000	PSIA
90	Oct 12, 2010 11:25:01 AM	1686.800	PSIA
91	Oct 12, 2010 11:29:59 AM	1690.200	PSIA



Report Name:	PrTemp1000 Data Table
Report Date:	Oct 12, 2010 02:20:41 PM MDT
File Name:	C:\Program Files\PTC® Instruments 2.00\Federal 15-12-9-17 ISIP (10-12-10).csv
Title:	Federal 15-12-9-17 ISIP (10-12-10)
Device:	PrTemp1000 - Temperature and Pressure Recorder
Hardware Revision:	REV2C (64K)
Serial Number:	M75866
Device ID:	PrTemp
Data Start Date:	Oct 12, 2010 11:31:22 AM MDT
Data End Date:	Oct 12, 2010 12:01:22 PM MDT
Reading Rate:	2 Seconds
Readings:	1 to 31 of 31
Last Calibration Date:	May 22, 2009
Next Calibration Date:	May 22, 2010

<u>Reading</u>	<u>Date and Time (MDT)</u>	<u>Absolute Pressure</u>	<u>Annotation</u>
1	Oct 12, 2010 11:31:22 AM	1689.000	PSIA
2	Oct 12, 2010 11:32:22 AM	1634.400	PSIA
3	Oct 12, 2010 11:33:21 AM	1611.600	PSIA
4	Oct 12, 2010 11:34:22 AM	1592.800	PSIA
5	Oct 12, 2010 11:35:22 AM	1578.600	PSIA
6	Oct 12, 2010 11:36:21 AM	1567.200	PSIA
7	Oct 12, 2010 11:37:22 AM	1555.400	PSIA
8	Oct 12, 2010 11:38:22 AM	1546.600	PSIA
9	Oct 12, 2010 11:39:22 AM	1538.200	PSIA
10	Oct 12, 2010 11:40:23 AM	1530.800	PSIA
11	Oct 12, 2010 11:41:22 AM	1523.400	PSIA
12	Oct 12, 2010 11:42:22 AM	1516.800	PSIA
13	Oct 12, 2010 11:43:22 AM	1512.000	PSIA
14	Oct 12, 2010 11:44:24 AM	1505.400	PSIA
15	Oct 12, 2010 11:45:22 AM	1500.800	PSIA
16	Oct 12, 2010 11:46:21 AM	1496.200	PSIA
17	Oct 12, 2010 11:47:22 AM	1491.400	PSIA
18	Oct 12, 2010 11:48:22 AM	1487.000	PSIA
19	Oct 12, 2010 11:49:21 AM	1483.400	PSIA
20	Oct 12, 2010 11:50:22 AM	1479.600	PSIA
21	Oct 12, 2010 11:51:22 AM	1476.200	PSIA
22	Oct 12, 2010 11:52:22 AM	1472.000	PSIA
23	Oct 12, 2010 11:53:22 AM	1468.800	PSIA
24	Oct 12, 2010 11:54:22 AM	1465.200	PSIA
25	Oct 12, 2010 11:55:22 AM	1462.000	PSIA
26	Oct 12, 2010 11:56:22 AM	1459.400	PSIA
27	Oct 12, 2010 11:57:22 AM	1456.000	PSIA
28	Oct 12, 2010 11:58:22 AM	1452.600	PSIA
29	Oct 12, 2010 11:59:21 AM	1450.200	PSIA
30	Oct 12, 2010 12:00:22 PM	1446.600	PSIA
31	Oct 12, 2010 12:01:22 PM	1443.600	PSIA

Federal 15-12-9-17 Rate Sheet (10-12-10)

<i>Step # 1</i>	Time:	4:35	4:40	4:45	4:50	4:55	5:00
	Rate:	100.5	100.5	100.5	100.5	100.5	100.4
	Time:	5:05	5:10	5:15	5:20	5:25	5:30
	Rate:	100.4	100.4	100.4	100.3	100.3	100.3
<i>Step # 2</i>	Time:	5:35	5:40	5:45	5:50	5:55	6:00
	Rate:	200.5	200.5	200.4	200.4	200.4	200.3
	Time:	6:05	6:10	6:15	6:20	6:25	6:30
	Rate:	200.3	200.3	200.3	200.3	200.3	200.2
<i>Step # 3</i>	Time:	6:35	6:40	6:45	6:50	6:55	7:00
	Rate:	300.4	300.4	300.4	300.4	300.3	300.3
	Time:	7:05	7:10	7:15	7:20	7:25	7:30
	Rate:	300.3	300.2	300.2	300.2	300.2	300.2
<i>Step # 4</i>	Time:	7:35	7:40	7:45	7:50	7:55	8:00
	Rate:	400.6	400.5	400.5	400.5	400.5	400.5
	Time:	8:05	8:10	8:15	8:20	8:25	8:30
	Rate:	400.4	400.4	400.3	400.3	400.3	400.3
<i>Step # 5</i>	Time:	8:35	8:40	8:45	8:50	8:55	9:00
	Rate:	500.7	500.7	500.7	500.6	500.6	500.6
	Time:	9:05	9:10	9:15	9:20	9:25	9:30
	Rate:	500.6	500.5	500.5	500.5	500.4	500.4
<i>Step # 6</i>	Time:	9:35	9:40	9:45	9:50	9:55	10:00
	Rate:	600.4	600.4	600.4	600.4	600.3	600.3
	Time:	10:05	10:10	10:15	10:20	10:25	10:30
	Rate:	600.3	600.2	600.2	600.2	600.1	600.1
<i>Step # 7</i>	Time:	10:35	10:40	10:45	10:50	10:55	11:00
	Rate:	700.5	700.4	700.4	700.3	700.3	700.3
	Time:	11:05	11:10	11:15	11:20	11:25	11:30
	Rate:	700.3	700.3	700.3	700.2	700.2	700.2
	Time:						
	Rate:						
	Time:						
	Rate:						

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-39713
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: FEDERAL 15-12-9-17
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0659 FSL 1981 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSE Section: 12 Township: 09.0S Range: 17.0E Meridian: S		9. API NUMBER: 43047351690000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: 8 MILE FLAT NORTH
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/26/2011	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input style="width: 100px;" type="text" value="5 YR MIT"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. On 09/14/2011 Nathan Wiser with the EPA was contacted concerning the 5 year MIT on the above listed well. On 09/26/2011 the casing was pressured up to 1040 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 1324 psig during the test. There was not an EPA representative available to witness the test. <div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;"> EPA# UT21029-06982 </div> <div style="text-align: center;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY </div> </div>		
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A	DATE 9/29/2011	

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 9 / 20 / 11
Test conducted by: Lynn Manson
Others present: _____

Well Name: <u>Federal 15-12-9-17</u>	Type: ER SWD	Status: AC TA UC
Field: <u>Monument Butte</u>		
Location: <u>SW/SE</u> Sec: <u>12</u> T <u>9</u> N <u>10</u> R <u>17</u> W	County: <u>Utah</u>	State: <u>ut</u>
Operator: <u>New Field</u>		
Last MIT: <u>/</u> / <u>/</u>	Maximum Allowable Pressure: _____	PSIG

Is this a regularly scheduled test? ☒ Yes ☐ No
Initial test for permit? ☐ Yes ☒ No
Test after well rework? ☐ Yes ☒ No
Well injecting during test? ☐ Yes ☒ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 0 psig


MIT DATA TABLE	Test #1	Test #2	Test #3
TUBING PRESSURE			
Initial Pressure	<u>1324</u> psig	psig	psig
End of test pressure	<u>1324</u> psig	psig	psig
CASING / TUBING ANNULUS PRESSURE			
0 minutes	<u>1040</u> psig	psig	psig
5 minutes	<u>1040</u> psig	psig	psig
10 minutes	<u>1040</u> psig	psig	psig
15 minutes	<u>1040</u> psig	psig	psig
20 minutes	<u>1040</u> psig	psig	psig
25 minutes	<u>1040</u> psig	psig	psig
30 minutes	<u>1040</u> psig	psig	psig
<u> </u> minutes	psig	psig	psig
<u> </u> minutes	psig	psig	psig
RESULT	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____



NEWFIELD



Schematic

43 047-35169

Well Name: Federal 15-12-9-17

Surface Legal Location 12-9S-17E		API/UWI 43047351690000		Well RC 500151465	Lease	State/Province Utah	Field Name GMBU CTB10	County Uintah
Spud Date 10/11/2004	Rig Release Date 12/2/2004	On Production Date 12/28/2004	Original KB Elevation (ft) 5,109	Ground Elevation (ft) 5,097	Total Depth All (TVD) (ftKB)		PBTD (All) (ftKB)	Original Hole - 5,712.9

Most Recent Job

Job Category Testing	Primary Job Type	Secondary Job Type N/A	Job Start Date 9/26/2011	Job End Date 9/26/2011
-------------------------	------------------	---------------------------	-----------------------------	---------------------------

TD: 5,767.0

Vertical - Original Hole, 1/14/2016 11:24:44 AM

MD (ftKB)	TVD (ftKB)	Incl (°)	DLS	Vertical schematic (actual)
			DLS (°...	
12.1				
259.8				
326.8				
327.8				
335.0				
3,999.3				
4,000.7				
4,007.9				
4,046.9				
4,062.0				
4,065.9				1; Surface; 8 5/8 in; 8,097 in; 12-328 ftKB; 315.71 ft
4,076.1				2-1; Tubing; 2 7/8; 2,441; 12-3,999; 3,987.48
4,734.9				2-2; Pump Seating Nipple; 2 7/8; 2,441; 3,999-4,001; 1.10
4,741.1				2-3; Packer; 5 1/2; 2,441; 4,001-4,008; 7.35
4,779.9				Perforated; 4,047-4,062; 12/22/2004
4,786.1				Perforated; 4,066-4,076; 12/22/2004
4,940.0				Perforated; 4,735-4,741; 12/22/2004
4,945.9				Perforated; 4,780-4,786; 12/22/2004
5,395.0				Perforated; 4,940-4,946; 12/22/2004
5,398.9				Perforated; 5,395-5,399; 12/21/2004
5,408.1				Perforated; 5,408-5,413; 12/21/2004
5,413.1				Perforated; 5,562-5,580; 12/16/2004
5,562.0				Perforated; 5,597-5,601; 12/16/2004
5,580.1				
5,597.1				
5,601.0				
5,712.9				
5,713.6				
5,752.6				
5,753.3				2; Production; 5 1/2 in; 4,950 in; 12-5,753 ftKB; 5,741.42 ft
5,767.1				

NEWFIELD



Newfield Wellbore Diagram Data Federal 15-12-9-17

Surface Legal Location 12-9S-17E		APN/Well 43047351690000		Lease	
County Uintah		State/Province Utah		Basin GMBU CTB10	
Well Start Date 10/11/2004		Spud Date 10/11/2004		Final Rig Release Date 12/2/2004	
Original KB Elevation (ft) 5,109		Ground Elevation (ft) 5,097		On Production Date 12/28/2004	
Total Depth (ftKB) 5,767.0		Total Depth All (TVD) (ftKB) 5,767.0		PBTD (All) (ftKB) Original Hole - 5,712.9	

Casing Strings

Csg Des	Run Date	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface	10/11/2004	8 5/8	8.097	24.00	J-55	328
Production	12/1/2004	5 1/2	4.950	15.50	J-55	5,753

Cement

String: Surface, 328ftKB 10/14/2004

Cementing Company BJ Services Company		Top Depth (ftKB) 12.0	Bottom Depth (ftKB) 335.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description w/ 2% CaCL2 + 1/4#/sk Cello-Flake		Fluid Type Lead	Amount (sacks) 150	Class G	Estimated Top (ftKB) 12.0

String: Production, 5,753ftKB 12/2/2004

Cementing Company BJ Services Company		Top Depth (ftKB) 260.0	Bottom Depth (ftKB) 5,767.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description w/ 10% gel + 3 % KCL. 3#'s /sk CSE + 2# sk/kolseal + 1/4#'s/sk Cello Flake		Fluid Type Lead	Amount (sacks) 285	Class Premite II	Estimated Top (ftKB) 260.0
Fluid Description W/ 2% Gel + 3% KCL. .5%EC1, 1/4# sk C.F. 2% gel. 3% SM		Fluid Type Tail	Amount (sacks) 400	Class 50/50 Poz	Estimated Top (ftKB) 3,000.0

Tubing Strings

Tubing Description					Run Date		Set Depth (ftKB)	
Tubing					10/16/2006		4,007.9	
Item Des	Jts	OD (in)	ID (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)
Tubing	123	2 7/8	2.441	6.50	J-55	3,987.48	12.0	3,999.5
Pump Seating Nipple		2 7/8	2.441			1.10	3,999.5	4,000.6
Packer		5 1/2	2.441			7.35	4,000.6	4,007.9

Rod Strings

Rod Description				Run Date		Set Depth (ftKB)	
Item Des	Jts	OD (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)

Perforation Intervals

Stage#	Zone	Top (ftKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (')	Nom. Hole Dia (in)	Date
5	GB6 sds, Original Hole	4,047	4,062	4	90	0.410	12/22/2004
5	GB6 sds, Original Hole	4,066	4,076	4	90	0.410	12/22/2004
4	B.5 sds, Original Hole	4,735	4,741	4	90	0.410	12/22/2004
4	B1 sds, Original Hole	4,780	4,786	4	90	0.410	12/22/2004
3	A1 sds, Original Hole	4,940	4,946	4	90	0.410	12/22/2004
2	CP2 sds, Original Hole	5,395	5,399	4	90	0.410	12/21/2004
2	CP2 sds, Original Hole	5,408	5,413	4	90	0.410	12/21/2004
1	CP4 sds, Original Hole	5,562	5,580	4		0.410	12/16/2004
1	CP5 sds, Original Hole	5,597	5,601	4		0.410	12/16/2004

Stimulations & Treatments

Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbl/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
1	1,280	0.66	24.8	1,346			
2	1,455	0.71	25.0	1,576			
3	2,000	0.84	24.7	2,192			
4	2,850	1.03	24.8	2,634			
5	2,300	1.0	24.6	2,076			

Proppant

Stage#	Total Prop Vol Pumped (lb)	Total Add Amount
1		Proppant Sand 40225 lb
2		Proppant Sand 29582 lb
3		Proppant Sand 14813 lb
4		Proppant Sand 48957 lb
5		Proppant Sand 69613 lb

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-39713
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052		8. WELL NAME and NUMBER: FEDERAL 15-12-9-17
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0659 FSL 1981 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSE Section: 12 Township: 09.0S Range: 17.0E Meridian: S		9. API NUMBER: 43047351690000
9. FIELD and POOL or WILDCAT: 8 MILE FLAT NORTH		COUNTY: UINTAH
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/31/2016 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:
		<input checked="" type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text" value="5 YR MIT"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 5 YR MIT performed on the above listed well. On 08/31/2016 the casing was pressured up to 1242 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbq pressure was 735 psig during the test. There was not an EPA representative available to witness the test. EPA #UT22197-06982

Accepted by the
Utah Division of
Oil, Gas and Mining

FOR RECORD ONLY

September 06, 2016

NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A	DATE 9/1/2016	

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 8 / 31 / 2016
Test conducted by: Shannon Lazenby
Others present: _____

Well Name: <u>Federal 15-12-9-17</u>	Type: ER SWD	Status: AC TA UC -06982
Field: <u>Greater Monument Butte</u>		
Location: <u>15-12-9-17</u> Sec: <u>12</u> T <u>95</u> N/S R <u>17</u> E/W County: <u>Utah</u> State: <u>ut</u>		
Operator: <u>Shannon Lazenby</u>		
Last MIT: <u> </u> / <u> </u> / <u> </u>	Maximum Allowable Pressure: <u>1257</u>	PSIG

Is this a regularly scheduled test? ☒ Yes ☐ No
Initial test for permit? ☐ Yes ☐ No
Test after well rework? ☐ Yes ☐ No
Well injecting during test? ☐ Yes ☒ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 0 / 735 psig

MIT DATA TABLE		Test #1	Test #2	Test #3
TUBING PRESSURE				
Initial Pressure	<u>735</u> psig	psig	psig	psig
End of test pressure	<u>735</u> psig	psig	psig	psig
CASING / TUBING ANNULUS PRESSURE				
0 minutes	<u>1241.0</u> psig	psig	psig	psig
5 minutes	<u>1241.2</u> psig	psig	psig	psig
10 minutes	<u>1241.4</u> psig	psig	psig	psig
15 minutes	<u>1241.2</u> psig	psig	psig	psig
20 minutes	<u>1241.4</u> psig	psig	psig	psig
25 minutes	<u>1241.2</u> psig	psig	psig	psig
30 minutes	<u>1241.8</u> psig	psig	psig	psig
_____ minutes	psig	psig	psig	psig
_____ minutes	psig	psig	psig	psig
RESULT	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____

15-12-9-17 5 year mit
8/31/2016 9:35:36 AM

